



JOHN ANDERSON, Jr. Governor
 RICHARD C. BYRD Chairman
 ALVIN F. GRAUERHOLZ Commissioner
 HARRY G. WILES Commissioner
 RAYMOND B. HARVEY Secretary
 CHARLES C. McCARTER Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
 500 Insurance Bldg. 212 N. Market
 WICHITA, KANSAS

RECEIVED
STATE CORPORATION COMMISSION

JUL 13 1962

CONSERVATION DIVISION
Wichita, Kansas

7-13-1962

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

J. P. Roberts
 Assistant Director
 500 Insurance Building
 212 North Market
 Wichita 2, Kansas

Dear Sir:

I have this date 10 July, 1962, authorized

The following plugging operation:

Operator's full Name: Amarillo Oil Co.

Complete Address: Box 151 Amarillo, Texas

Lease Name: C.F. Wright Well No. 1

Location: C SE NE Sec. 33 Twp. 21S Rge. 34 (R) (W)

County Finney Total Depth: 4860

Oil Well Gas Well Input Well SWD Well

D & A Other well as hereafter indicated: _____

Operator was instructed to plug well as follows:

~~8 5/8" 402' Cem. w/cem. 4 1/2" 4439' cem. w/120 sax. Bridge at 4210'~~
~~Heavy mud 4210' to 4050' Cem. 10 sax. 4050' to 3950' w/plug.~~
~~Heavy mud 3950' to 450' Cem. 50 sax. w/plug 450' to 350'~~
~~Heavy mud 350' to 40' Cem. 15 sax. and plug to top of hole.~~

Very truly yours,
Hugh Scott

