

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 200 Colorado Derby Building
 Wichita, Kansas 67202

WELL PLUGGING RECORD
 K.A.R.--82-3-117

API NUMBER 15-185-20,809.0000

LEASE NAME Williamson

WELL NUMBER #3

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

4900 Ft. from S Section Line

4950 Ft. from E Section Line

SEC. 34 TWP. 21 RGE. 12 (E) or (W)

COUNTY Stafford

LEASE OPERATOR Woodman & Iannitti Oil Co.

ADDRESS Box 308, Great Bend, Ks. 67530

PHONE# (316-792-1934) OPERATORS LICENSE NO. 6588

Date Well Completed _____

Character of Well SWD

Plugging Commenced 10-2-86

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 10-13-86

Did you notify the KCC District Office prior to plugging this well? Yes

Which KCC Office did you notify? One (1)

Is ACO-1 filed? _____ If not, is well log attached? With application

Producing Formation _____ Depth to Top _____ Bottom _____ T.D. 3740'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8-5/8"	293'	None
				5-1/2"	3640'	2,698.93'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.
 Dumped sand to 3350' and 5 sacks cement. Shot casing at 2900' and 2700'. Pulled 86 joints of 5-1/2" casing. B.J. Titan squeezed well with 3 sacks hulls, 40 sacks gel and 100 sacks Econolite cement. Maximum pressure was 600 psi and shutin 350 psi.

Name of Plugging Contractor Rockhold Engineering, Inc. License No. 5111

Address Box 698, Great Bend, Kansas 67530

STATE OF Kansas COUNTY OF Barton, ss.

James W. Rockhold

(Employee of Operator) or (Operator) of

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct.

RECEIVED
 STATE CORPORATION COMMISSION
 CONS. DIV. WICHITA, KANSAS

(Signature) James W. Rockhold

(Address) James W. Rockhold
Box 698, Gt. Bend, Ks. 67530

SUBSCRIBED AND SWORN TO before me this 14th day of October, 1986

OCT 15

Jona M. Leatherman
 Notary Public

My Commission Expires:

