

STATE OF KANSAS  
STATE CORPORATION COMMISSION

Form CP-4

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
212 No. Market  
Wichita, Kansas

Stafford County, Sec. 12 Twp. 21 Rge. 12 (E) (W) X

Location as "NE/CNW/SW" or footage from lines SW/4 NE/4 NE/4

Lease Owner Duke Drilling Company

Lease Name Hall Well No. 2

Office Address P. O. Box 823 Great Bend, Kansas

Character of Well (completed as Oil, Gas or Dry Hole)

Date well completed 19

Application for plugging filed 10-17-66 19

Application for plugging approved 10-18-66 19

Plugging commenced 11-4-66 19

Plugging completed 11-17-66 19

Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Archie V. Elving

Producing formation Depth to top Bottom Total Depth of Well 3500 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	281	None
				4 1/2	None	2764

NOV 28 1966  
CONSERVATION DIVISION  
WICHITA, KANSAS

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Moved in. Rigged up.

Sanded to 3400'. Dumped 4 sacks of cement. Working pipe. Shot pipe at 3010'.

Circulating. Spotted 60 bbl of oil. Shot pipe at 2850' and 2755'.

Working pipe. Pulling pipe.

Pushed plug to 275' rock bridge. Dumped 10 sacks of cement.

Bailed hole dry. Dumped 15 sacks of cement. Filled hole and rock bridge. Capped well with 10 sacks of cement.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Forbes Casing Pulling, Inc.

Address P. O. Box 221 Great Bend, Kansas 67530

STATE OF Kansas, COUNTY OF Barton, ss.

J. O. Forbes (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) J. O. Forbes

P. O. Box 221 Great Bend, Kansas (Address)

SUBSCRIBED AND SWORN TO before me this 21 day of November, 1966

My commission expires May 27, 1969

Notary Public.

WELL LOG

Date Commenced: August 22, 1966  
Date Completed: August 31, 1966

Duke Drilling Company  
HALL #2  
SW/4 NE/4 NE/4 Sec. 12-21-12N  
Stafford Co., Kansas

- 0 - 190' Clay & Sand
- 190 - 285' Shale Sand Shells Red
- 285 - 584' Red Bed
- 584 - 610' ANHYDRITE
- 610 - 1285' Shale Shells Salt
- 1285 - 1575' Shale Lime
- 1575 - 1945' Lime Shale
- 1945 - 2660' Shale Lime
- 2660 - 3027' Lime Shale
- 3027 - 3031' Shale
- 3031 - 3047' Lime Shale
- 3047 - 3060' Lime
- 3060 - 3154' Shale
- 3154 - 3168' Lime - Shale
- 3168 - 3415' Lime
- 3415 - 3428' Conglomerate
- 3428 - 3450' Shale & Sand
- 3450 - 3502' Dolomite

ELEVATION: 1814 K.B.

FORMATION DATA

Anhydrite	584
Heebner	3027
Lansing	3168
Simpson	3428
Arbuckle	3450
R.T.D.	3502

RECEIVED  
STATE CORPORATION COMMISSION

OCT 18 1966

CONSERVATION DIVISION  
W. P. C. Helgeson


Surface Pipe: Set 8-5/8" @ 281'  
with 325 sacks cement.

Production Casing: Set 4 1/2"  
casing at 3500' with 75 sacks  
cement & 300 gal latex  
cement.

AFFIDAVIT

STATE OF KANSAS - COUNTY OF BARTON ) ss:

L. O. Chubb, of lawful age, does swear and state that the facts and statements herein contained are true and correct to the best of his knowledge.

  
L. O. Chubb

Subscribed and sworn to before me this 1 day of September, 1966

My Comm. Expires: 4-11-70

  
Dorothy M. Hague-NOTARY PUBLIC