

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-051-19190-00-01
Spot: SESWNE Sec/Twnshp/Rge: 12-13S-20W
2935 feet from S Section Line, 1590 feet from E Section Line
Lease Name: JACQUES Well #: 1
County: ELLIS Total Vertical Depth: 3825 feet

Operator License No.: 32062
Op Name: ARDC INC.
Address: 108 W 34TH ST
HAYS, KS 67601

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3833		150 SX
SURF	8.826	259		175 SX

Well Type: OIL UIC Docket No: Date/Time to Plug: 07/27/2017 1:00 PM
Plug Co. License No.: 32810 Plug Co. Name: PROFESSIONAL PULLING SERVICES LLC
Proposal Rcvd. from: GREG WHITEHAIR Company: ARDC INC. Phone: (785) 625-6588

Proposed Plugging Method: Casing leaks at 1300' and 1400'.
Perforations: 3423' - 3668' and 3610' - 3614'.
Sanded off bottom to 3463'. Tied to MIT well for TA purposes.

Plugging Proposal Received By: PAT STAAB WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 07/27/2017 8:00 PM KCC Agent: PAT STAAB

Actual Plugging Report:

Perfs:

Pioneer perforated at 2050', 1457' nad 736'. Professional ran in hole with tubing to 3310' and pumped 130 sx cement w/250 # hulls mixed in. Pulled tubing to 2050' and pumped 125 sx cement w/150 # hulls mixed in. Pulled tubing to 1025' and pumped 55 sx cement w/100 # hulls mixed in to circulate cement to surface. Pulled tubing. Rigged to 5 1/2" production casing and pumped 20 sx cement at 200 psi. Shut in pressure 200 psi. Rigged to 8 5/8" surface casing and pumped 10 sx cement at 200 psi. Shut in pressure 200 psi.

GPS: 38.93678 -099.48958

KCC WICHITA
AUG 24 2017
RECEIVED


Remarks: PRECISION DRILLING AND HESS SERVICES TICKET # 704704

Plugged through: TBG

INVOICED
AUG 30 2017

District: 04

Signed



(TECHNICIAN)

CJA

AUG. 03, 2017