

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-065-30181-00-00
Spot: NWSW Sec/Twnshp/Rge: 31-6S-25W
1980 feet from S Section Line, 4620 feet from E Section Line
Lease Name: WARD LEASE Well #: 1
County: GRAHAM Total Vertical Depth: 3880 feet

Operator License No.: 34318
Op Name: BEREXCO LLC
Address: 2020 N. BRAMBLEWOOD
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	3880		50 SX
SURF	8.625	259		200 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 07/27/2017 10:00 AM
Plug Co. License No.: 3152 Plug Co. Name: POE SERVICING INC
Proposal Rcvd. from: MARK LEIKER Company: BEREXCO LLC Phone: (316) 772-8649

Proposed Plugging Method: Ordered 400 sx 60/40 pozmix 4% gel cement w/600 # hulls.
Perforations: 3676' - 3794'.
DV Tool at 2172' w/1000 sx cement.

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 07/27/2017 12:30 PM KCC Agent: MARVIN MILLS

Actual Plugging Report:

Ran tubing to 3787' and pumped 75 sx cement w/250 # hulls. Pulled tubing to 2793' and pumped 75 sx cement w/100 # hulls. Pulled tubing to 1775' and pumped 75 sx cement w/100 # hulls. Pulled tubing to 787' and pumped 75 sx cement. Cement circulated. Pulled tubing out. Topped off casing with 15 sx cement. Tied on to backside and squeezed with 60 sx cement. Shut in pressure 50 psi.

GPS: 39.48547 -100.15977

Perfs:

KCC WICHITA
AUG 24 2017
RECEIVED

INVOICED
AUG 30 2017

Remarks: GLOBAL CEMENT TICKET # 3058

Plugged through: TBG

District: 04

Signed _____

Marvin Mills
(TECHNICIAN)

CM

AUG 03 2017