

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-191-10725-00-00  
Spot: SEENWNNE Sec/Twnshp/Rge: 25-31S-2E  
4841 feet from S Section Line, 1604 feet from E Section Line  
Lease Name: WILES Well #: 10 TWIN  
County: SUMNER Total Vertical Depth: 1695 feet

Operator License No.: 35191  
Op Name: BUFFALO OIL & GAS, LLC  
Address: 119 N. MICHIGAN ST. PO BOX 6  
OXFORD, KS 67119

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		1695		
PROD	4.5	1890		150 SX
SURF	8.625	218		175 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 05/23/2017 8:00 AM  
Plug Co. License No.: 3004 Plug Co. Name: GRESSEL OILFIELD SERVICE, LLC  
Proposal Rcvd. from: DON SHORT Company: BUFFALO OIL & GAS LLC Phone: (620) 218-1809

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: DAN FOX Witness Type: PARTIAL  
Date/Time Plugging Completed: 05/24/2017 6:00 PM KCC Agent: DAN FOX

Actual Plugging Report:

RAN IN TUBING TO 1600' PUMPED 50 SX OF COMMON W/4% CC FOR BOTTOM PLUG, PULLED TUBING WAITED FOR 1 HOUR AND RAN BACK IN WITH WIRE-LINE AND PERFORATED CASING AT 300' WITH 4 SHOTS, RAN DOWN TAGGED TOP OF BOTTOM PLUG AT 1440'. RAN BACK IN WITH TUBING TO 300' AND PUMPED 165 SX OF 60/40 POS-MIX WITH 2% GEL. COPELAND ACID & CEMENT TICKET #44942. CASING STOOD FULL, JOB COMPLETE.

Perfs:

Top	Bot	Thru	Comments
1832	1836	TBG	

INVOICED  
AUG 30 2017

Remarks: NOTE: WELL WAS PLUGGED UNDER COMPLIANCE AGREEMENT DOCKET #17-CONS-3659-CMSC

Plugged through: TBG

District: 02

Signed \_\_\_\_\_

(TECHNICIAN)