

TO:

STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-207-02397-00-00

Spot: N2NE

Sec/Twnshp/Rge: 27-26S-14E

4620 feet from S Section Line, 1320 feet from E Section Line

Lease Name: MCALLISTER

Well #: 1

County: WOODSON

Total Vertical Depth: 1386 feet

Operator License No.: 5150

Op Name: COLT ENERGY INC

Address: PO BOX 388
IOLA, KS 66749

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		1351		
PROD	4.5	1393		50 SX
SURF	7	65		12 SX

Well Type: OIL

UIC Docket No:

Date/Time to Plug: 07/28/2017 2:39 PM

Plug Co. License No.: 5491

Plug Co. Name: W & W PRODUCTION COMPANY, GENERAL PARTNERSHIP

Proposal Rcvd. from: REX R. ASHLOCK

Company:

Phone: (620) 365-3111

Proposed Plugging Method: RIH 1" TBG ON "BACKSIDE" OF THE 4 1/2" PROD CSG (ANNULAS) AS FAR AS WE CAN GET (MIN AT LEAST 250" THEN CIRC CMT TO SURF, POOH 1" TUB. NEXT: RIH 2 3/8" INSIDE THE PROD CSG TO 1282' (THE CO TD IN MARCH OF 1958 "SLM"), "GEL" THE WELL UP (PMP IN A MIXTURE OF BENTONITE & WTR), FOLLOWED BY A 250' CMT PLUG ON BTM. PU TBG TO 750', PMP IN A 50' CMT PLUG, PU TBG TO 250', PMP IN & CIRC CMT TO SURF, POOH REST OF TBG, "TOP OFF" PROD CSG AND ANY VOID ON "BACKSIDE" OF PROD CSG. WILL RETURN AT A LATER DATE TO CUT OFF ALL CSG BELOW "FLOW DEPTH" AND CLEAN UP LOC.

Plugging Proposal Received By: MICHAEL HEFFERN

Witness Type: NONE

Date/Time Plugging Completed: 07/31/2017 4:30 PM

KCC Agent: MICHAEL HEFFERN

Actual Plugging Report:

Ran 1" down backside of casing to 250' circ cement to surface, ran tubing to 1282', pumped 250' cement plug, pulled tubing to 750' pumped 50' cement plug, pulled tubing to 250', circ cement to surface.

Perfs:

Top	Bot	Thru	Comments
1271	1281		

RECEIVED
KCC DIST # 3
AUG 28 2017
CHANUTE, KS

MT
INVOICED
AUG 30 2017

Remarks:

Plugged through: TBG

District: 03

Signed

Michael Heffern
(TECHNICIAN)