

TO:

STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-207-02399-00-00

Spot: SWNENWNE

Sec/Twnshp/Rge: 27-26S-14E

638 feet from N Section Line,

1654 feet from E Section Line

Lease Name: MCALLISTER

Well #: 2A

County: WOODSON

Total Vertical Depth: 1340 feet

Operator License No.: 5150

Op Name: COLT ENERGY INC

Address: PO BOX 388
IOLA, KS 66749

String	Size	Depth (ft)	Pulled (ft)	Comment
--------	------	------------	-------------	---------

PROD	4.5	1339		55 SX
------	-----	------	--	-------

SURF	6.625	229		15 SX
------	-------	-----	--	-------

Well Type: OIL

UIC Docket No:

Date/Time to Plug: 07/28/2017 8:00 AM

Plug Co. License No.: 5491

Plug Co. Name: W & W PRODUCTION COMPANY, GENERAL PARTNERSHIP

Proposal Rcvd. from: REX R. ASHLOCK

Company:

Phone: (620) 365-3111

Proposed Plugging Method: RIH 1" TBG ON "BACKSIDE" OF PROD CSG (ANNULAS) TO DEEP AS CAN GO (MIN OF 250'), PMP IN AND CIRC CMT TO SURF, POOH 1" TBG, THEN; RIH 2 3/8" TBG TO 1339', "GEL" HOLE UP (PMP IN A MIXTURE OF BENTONITE & WTR), FOLLOWED BY A 250' CMT PLUG ON BTM, PU TBG TO 760', PMP IN A 50' CMT PLUG, PU TBG TO 250', PMP AND CIRC CMT TO SURF, POOH REST OF TBG AND "TOP OFF" WELL W/ CMT. RETURN AT A LATER DATE. CUT OFF ALL CSG BELOW "PLOW DEPTH" AND CLEAN UP THE LOC.

Plugging Proposal Received By: MICHAEL HEFFERN

WitnessType: NONE

Date/Time Plugging Completed: 07/31/2017 12:00 PM

KCC Agent: MICHAEL HEFFERN

Actual Plugging Report:

Ran 1" on backside of casing to 250', circ cement to surface, ran tubing to 1339', pumped 250' cement plug, pulled tubing to 750', pumped 50' cement plug, pulled tubing to 250', circ cement to surface.

Perfs:

Top	Bot	Thru	Comments
1263	1281		

RECEIVED
KCC DIST # 3

AUG 28 2017

CHANUTE, KS

MH

INVOICED

AUG 30 2017

Remarks:

Plugged through: TBG

District: 03

Signed

Miko Heffern

(TECHNICIAN)