

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-207-23679-00-00
Spot: NWNWNE Sec/Twnshp/Rge: 27-26S-14E
250 feet from N Section Line, 1010 feet from E Section Line
Lease Name: MCALLISTER Well #: 3A
County: WOODSON Total Vertical Depth: 1363 feet

Operator License No.: 5150
Op Name: COLT ENERGY INC
Address: PO BOX 388
IOLA, KS 66749

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	1362		205 SX
SURF	8	50		25 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 07/31/2017 8:00 AM
Plug Co. License No.: 5491 Plug Co. Name: W & W PRODUCTION COMPANY, GENERAL PARTNERSHIP
Proposal Rcvd. from: REX R. ASHLOCK Company: _____ Phone: (620) 365-3111

Proposed Plugging Method: RIH 2 3/8" TBG TO 1361', "GEL" THE WELL UP (PMP IN A MIXTURE OF BENTONITE AND WTR) FOLLOWED BY 250' CMT PLUG ON BTM, PU TBG TO 740', PMP IN A 50' CMT PLUG, PU TBG TO 250', PMP IN AND CIRC CMT TO SURF, POOH REST OF TBG, "TOP OFF" WELL W/ CMT, AND SHUT WELL IN (SWI). RETURN AT A LATER DATE, CUT OFF ALL CSG BELOW "PLOW DEPTH" AND CLEAN UP LOC.

Plugging Proposal Received By: MICHAEL HEFFERN Witness Type: NONE
Date/Time Plugging Completed: 07/31/2017 10:00 AM KCC Agent: MICHAEL HEFFERN

Actual Plugging Report:

Ran tubing to 1361', pumped 250' cement plug, pulled tubing to 740', pumped 50' cement plug, pulled tubing to 250' circ. Cement to surface

Perfs:

Top	Bot	Thru	Comments
1339	1342		

RECEIVED
KCC DIST # 3
AUG 28 2017
CHANUTE, KS

MH

INVOICED
AUG 30 2017

Remarks:

Plugged through: TBG

District: 03

Signed Mike Heffern
(TECHNICIAN)