

TO:

STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-207-02384-00-00

Spot: E2W2SWSE

Sec/Twnshp/Rge: 22-26S-14E

660 feet from S Section Line, 2100 feet from E Section Line

Lease Name: COBBLE

Well #: 1A

County: WOODSON

Total Vertical Depth: 1350 feet

Operator License No.: 5150

Op Name: COLT ENERGY INC

Address: PO BOX 388
IOLA, KS 66749

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	1350		251 SX
SURF	7	195		75 SX

Well Type: GAS

UIC Docket No:

Date/Time to Plug: 07/31/2017 8:30 AM

Plug Co. License No.: 5491

Plug Co. Name: W & W PRODUCTION COMPANY, GENERAL PARTNERSHIP

Proposal Revd. from: REX R. ASHLOCK

Company:

Phone: (620) 365-3111

Proposed Plugging Method: RIH 2 3/8" TBG TO 1349', "GEL" THE WELL UP (PMP IN A MIXTURE OF BENTONITE & WTR), FOLLOWED BY A 300' CMT PLUG ON BTM, PU TBG TO 740', PMP IN A 50' CMT PLUG, PU TBG TO 250', PMP IN CMT AND CIRC SAME TO SURF. POOH REST OF TBG, "TOP OFF" WELL W/ CMT AND SIW. RETURN AT A LATER DATE, CUT OFF ALL CSG BELOW "PLOW DEPTH" AND CLEAN UP THE LOC.

Plugging Proposal Received By: MICHAEL HEFFERN

WitnessType: NONE

Date/Time Plugging Completed: 07/31/2017 10:30 AM

KCC Agent: MICHAEL HEFFERN

Actual Plugging Report:

Ran tubing to 1339', pumped 300' cement plug, pulled tubing to 740', pumped 50' cement plug, pulled tubing to 250' circ. Cement to surface

Perfs:

Top	Bot	Thru	Comments
1238	1255		

RECEIVED
KCC DIST # 3
AUG 28 2017
CHANUTE, KS

MH

INVOICED
AUG 30 2017

Remarks:

Plugged through: TBG

District: 03

Signed

Mike [Signature]
(TECHNICIAN)