

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-099-19378-00-00
Spot: NWSWSW Sec/Twnshp/Rge: 2-33S-17E
671 feet from S Section Line, 5076 feet from E Section Line
Lease Name: KERR-BLANKENSHIP TRUST Well #: 2
County: LABETTE Total Vertical Depth: 780 feet

Operator License No.: 5150
Op Name: COLT ENERGY INC
Address: PO BOX 388
IOLA, KS 66749

| String | Size | Depth (ft) | Pulled (ft) | Comment |
|--------|------|------------|-------------|---------|
| PROD | 4.5 | 772 | | 97 SX |
| SURF | 7 | 20 | | 4 SX |

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 08/15/2017 12:00 AM
Plug Co. License No.: 5491 Plug Co. Name: W & W PRODUCTION COMPANY, GENERAL PARTNERSHIP
Proposal Rcvd. from: REX R. ASHLOCK Company: _____ Phone: (620) 365-3111

Proposed Plugging Method: RIH 2 3/8" TBG TO WITHIN 1' OF BTM OF CSG, "GEL" THE WELL UP (PMP IN A MIXTURE OF BENTONITE & WTR), THEN PMP IN A 100' CMT PLUG ON BTM, PU TBG TO 500', PMP IN A 50' CMT PLUG, PU TBG TO 250', PMP IN AND CIRC CMT TO THE SURFACE, POOH REST OF TBG, "TOP OFF" WELL WITH CMT, AND SHUT WELL IN (SWI). RETURN AT A LATER DATE, CUT OFF ALL CSG BELOW "PLOW DEPTH" AND CLEAN UP LOC.

Plugging Proposal Received By: _____ WitnessType: NONE
Date/Time Plugging Completed: 08/15/2017 12:00 AM KCC Agent: RUSSELL HINE

Actual Plugging Report:

RIH 2 3/8" TBG TO 772', "GEL'D THE WELL UP" (PMPD IN A MIXTURE OF BENTONITE & WTR), FOLLOWED BY A 100' CMT PLUG ON BTM, PU TBG TO 446', PMPD IN A 50' CMT PLUG, PU TBG TO 250', PMPD IN & CIRC CMT TO SURF, POOH REST OF TBG, "TOPPED OFF" PRODUCTION CSG W/ CMT, SWI.CMT FROM 772 TO 672, GEL SPACER FROM 672 TO 446, CMT FROM 446 TO 496, GEL SPACER FROM 496 TO 250, CMT FROM 250 TO SURF.USED; 2, 100# SX OF BENTONITE, 1/2 SX OF COTTON SEED HULLS, 62 SX OF PORTLAND CMT W/ NO ADDITIVES.

Perfs:

| Top | Bot | Thru | Comments |
|-----|-----|------|----------|
| 752 | 770 | | |

RECEIVED
KCC DIST # 3
AUG 24 2017
CHANUTE, KS

RH

INVOICED
AUG 30 2017

Remarks: THIS WELL IS LISTED ON A COMPLIANCE AGREEMENT

Plugged through: TBG

District: 03

Signed Russell Hine
(TECHNICIAN)