

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-099-24653-00-00
Spot: NESWNWSW Sec/Twnshp/Rge: 2-33S-17E
1847 feet from S Section Line, 505 feet from W Section Line
Lease Name: GREGORY Well #: 12-2
County: LABETTE Total Vertical Depth: 1051 feet

Operator License No.: 5150
Op Name: COLT ENERGY INC
Address: PO BOX 388
IOLA, KS 66749

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	1023		125 SX
SURF	8.625	21		4 SX

Well Type: CM UIC Docket No: _____ Date/Time to Plug: 08/15/2017 12:00 AM
Plug Co. License No.: 5491 Plug Co. Name: W & W PRODUCTION COMPANY, GENERAL PARTNERSHIP
Proposal Rcvd. from: REX R. ASHLOCK Company: _____ Phone: (620) 228-2847

Proposed Plugging Method: RIH 2 3/8" TBG TO 1022', "GEL" WELL UP (PMP IN A MIXTURE OF BENTONITE & WTR) THEN PMP IN A 100' CMT PLUG ON BTM, PU TBG TO 600', PMP IN A 50' CMT PLUG, PU TBG TO 250', PMP IN & CIRC CMT TO SURF, POOH REST OF TBG, "TOP OFF" WELL W/ CMT, & SWI. RETURN AT A LATER DATE, CUT OFF ALL CSG BELOW "PLOW DEPTH" AND CLEAN UP LOC.

Plugging Proposal Received By: _____ WitnessType: NONE
Date/Time Plugging Completed: 08/15/2017 12:00 AM KCC Agent: RUSSELL HINE

Actual Plugging Report:

Perfs:

RIH 2 3/8" TBG TO 1022', HIT TOP OF CMT PLUG, PU TBG 1', "GEL'D THE WELL UP" (PMPD IN A MIXTURE OF BENTONITE & WTR), FOLLOWED BY A 150' CMT PLUG ON BTM, PU TBG TO 600', PMPD IN A 100' CMT PLUG, PU TBG TO 252', PMPD IN AND CIRC CMT TO SURF, POOH REST OF TBG, "TOPPED OFF" PROD CSG W/ CMT, PRESS UP TO 100 PSI AND SWI. CMT FROM 1022 TO 872, GEL SPACER FROM 872 TO 600, CMT FROM 600 TO 500, GEL SPACER FROM 500 TO 252, CMT FROM 252 TO SURF. USED: 2, 100# SX OF BENTONITE AND 57 SX OF PORTLAND CMT W/ NO ADDITIVES

RECEIVED
KCC DIST #3
AUG 24 2017
CHANUTE, KS

RH

Remarks: THIS WELL IS LISTED ON A COMPLIANCE AGREEMENT

Plugged through: TBG

District: 03

Signed

Russell Hine
(TECHNICIAN)

INVOICED
AUG 30 2017