

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-019-20760-00-00
Spot: NWNWNW Sec/Twnshp/Rge: 22-34S-11E
4987 feet from S Section Line, 4931 feet from E Section Line
Lease Name: WILSON Well #: 14
County: CHAUTAUQUA Total Vertical Depth: 1320 feet

Operator License No.: 7785

Op Name: DILLEY, W.R. & A'META I.

Address: 658 RD 19
SEDAN, KS 67361

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	7	1320		
SURF	10	40		

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 07/24/2017 12:00 AM

Plug Co. License No.: 32884 Plug Co. Name: ELMORE'S, INC.

Proposal Revd. from: A'META I. DILLEY Company: _____ Phone: (620) 725-3958

Proposed Plugging Method: SURFACE AND PRODUCTION CASING CMT UNKNONWN. PLUG ACCORDING TO KCC INSTRUCTIONS.

Plugging Proposal Received By: DUANE SIMS Witness Type: NONE
Date/Time Plugging Completed: 07/25/2017 12:00 PM KCC Agent: DUANE SIMS

Actual Plugging Report:

Ran 1" to 1200' gelled hole and spotted 5 sack plug. Pulled up to 800' and spotted 5 sack plug. Pulled up to 350' and circulated cement to surface with 35 sacks of cement. Ran down backside of casing to 150' and tagged cement. Circulated 135 sacks of cement to surface. Pulled 1" and topped inside and outside of well off. A total of 180 sacks of cement were used to plug this well. Well was cut off and location restored.

Perfs:

Top	Bot	Thru	Comments
1250	1260		

RECEIVED
KCC DIST # 3
AUG 22 2017
CHANUTE, KS
DS

Remarks: OPERATOR PLUGGED ALL WELLS ON LICENSE #7785.

Plugged through: TBG

INVOICED
AUG 30 2017

District: 03

Signed *D. Sims*
(TECHNICIAN)