

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-019-20443-00-00
Spot: SENWNW Sec/Twnshp/Rge: 22-34S-11E
4402 feet from S Section Line, 4119 feet from E Section Line
Lease Name: WILSON Well #: 12
County: CHAUTAUQUA Total Vertical Depth: 1315 feet

Operator License No.: 7785

String Size Depth (ft) Pulled (ft) Comment

Op Name: DILLEY, W.R. & A'META I.

PROD 4.5 1315

Address: 658 RD 19
SEDAN, KS 67361

SURF 8.625 40

Well Type: OIL

UIC Docket No:

Date/Time to Plug: 07/23/2017 12:00 AM

Plug Co. License No.: 32884

Plug Co. Name: ELMORE'S, INC.

Proposal Revd. from: A'META I. DILLEY

Company:

Phone: (620) 725-3958

Proposed
Plugging
Method:

SURFACE AND PRODUCTION CASING CMT UNKNONWN. PLUG ACCORDING TO KCC INSTRUCTIONS.

Plugging Proposal Received By: DUANE SIMS

Witness Type: NONE

Date/Time Plugging Completed: 07/24/2017 10:00 AM

KCC Agent: DUANE SIMS

Actual Plugging Report:

Ran 1" 1200' gelled hole and spotted 5 sack plug. Pulled up to 700' and spotted 5 sack plug. Pulled up to 350' and circulated cement to surface with 35 sacks of cement. Ran down backside of casing to 70' and tagged cement. Circulated 15 sacks of cement to surface on backside of casing. A total of 60 sacks of cement were used to plug this well. Well was cut off and location restored.

Perfs:

Top	Bot	Thru	Comments
1250	1260		

RECEIVED
KCC DIST # 3
AUG 22 2017
CHANUTE, KS

DS

Remarks: OPERATOR PLUGGED ALL WELLS ON LICENSE #7785.


INVOICED

Plugged through: TBG

AUG 30 2017

District: 03

Signed



(TECHNICIAN)