

TO:

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-007-21797-00-01

Spot: W2SWSENE

Sec/Twnshp/Rge: 36-31S-12W

2970 feet from S Section Line, 1245 feet from E Section Line

Lease Name: HOAGLAND

Well #: 2

County: BARBER

Total Vertical Depth: 4380 feet

Operator License No.: 5316

Op Name: FALCON EXPLORATION, INC.

Address: 125 N MARKET STE 1252  
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
--------	------	------------	-------------	----------

CIBP		3560		WITH 2 SX CMT
------	--	------	--	---------------

CIBP		4320		WITH 2 SX CMT
------	--	------	--	---------------

PROD	4.5	4365	2270	WITH 250 SX CMT
------	-----	------	------	-----------------

SURF	8.625	264		WITH 300 SX CMT
------	-------	-----	--	-----------------

Well Type: OG

UIC Docket No:

Date/Time to Plug: 08/18/2017 11:00 AM

Plug Co. License No.: 34484

Plug Co. Name: FOSSIL DRILLING, INC.

Proposal Revd. from: KELLY SCHMEIDLER

Company: EXCEL WIRELINE

Phone: (620) 546-4752

Proposed  
Plugging  
Method:

SET CIBP @ 4320' WITH 2 SX CMT. SET CIBP @ 3560' WITH 2 SX CMT. PLUG AT 600' WITH 10 SX GEL & 50 SX CMT. PLUG AT 300' WITH 50 SX CMT. PLUG AT 40' WITH 20 SX CMT.

Plugging Proposal Received By: KENNY SULLIVAN

Witness Type: COMPLETE (100%)

Date/Time Plugging Completed: 08/18/2017 12:15 PM

KCC Agent: STEVE PFEIFER

Actual Plugging Report:

Perfs:

SET CIBP'S AT 3560' & 4320'. PUT 2 SX CMT ON TOP OF EACH CIBP THOURHG DUMP BAILER. 1ST PLUG AT 612' WITH 10 SX GEL & 50 SX CMT. 2ND PLUG AT 318' WITH 50 SX CMT. 3RD PLUG AT 42' WITH 20 SX CMT.

Top	Bot	Thru	Comments
3609	3617		

Remarks: USED 60/40 POZMIX 4% GEL BY GLOBAL OILFIELD.

Plugged through: CSG

INVOICED  
AUG 29 2017

District: 01

Signed

*Stephen J Pfeifer*  
5A  
(TECHNICIAN)

RECEIVED  
AUG 21 2017  
KCC DODGE CITY