



15-009-21509-0000

## State Corporation Commission

## CONSERVATION DIVISION

(Oil, Gas and Water)

245 North Water  
WICHITA, KANSAS 67202VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)RECEIVED  
STATE CORPORATION COMMISSION

NOV 30 1978

CONSERVATION DIVISION  
Wichita, KansasJ. Lewis Brock  
Administrator  
245 North Water  
Wichita, Kansas 67202

Dear Sir:

Mr. Smith of Allen Drlg. Co. has this  
date requested permission to plug the following described well:Mr. Smith guarantees payment of the plugging fee.Operator's full Name: Bankoff Oil Co.Complete Address: Drawer 2479 Tulsa, Okla.Lease Name: Kraft Well No. 2Location: SE NW NW Sec. 36 Twp. 16 Rge. 11 ~~(E)~~ (W) XCounty: Barton Total Depth 3385' Oil WellGas Well      Input Well      SWD Well      D & A X Lost Hole     Mr. Smith was instructed to plug the well as follows:Fill hole with mud and spot 50 sx cement at 400'.Fill hole with mud to 40' and  $\frac{1}{2}$  sx hulls, plug,and 10 sx cement.2 sx cement in rat hole.355' of 9 5/8" surface casing cement circ.

Very truly yours,

  
Conservation Division Agent