

State of Kansas



FORM - CP-2  
Rev. 9-8-64

15.185.19502.0001

WM. H. AVERY Governor  
WILLIAM L. MITCHELL Chairman  
JOHN C. WOELK Commissioner  
HARRY G. WILES Commissioner  
RAYMOND B. HARVEY Secretary  
E. EDWARD JOHNSON Gen. Counsel

# State Corporation Commission

## CONSERVATION DIVISION

(Oil, Gas and Water)  
500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

RECEIVED  
STATE CORPORATION COMMISSION

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

DEC - 1 1965

CONSERVATION DIVISION  
Wichita, Kansas

12-1-1965

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita 2, Kansas

Dear Sir:

Mr. A. C. Arnott of Jay Bergman Oil Company has this date requested permission to plug the following described well:

Mr. Arnott guarantees payment of the plugging fee.

Operator's full Name: Jay Bergman Oil Company

Complete Address: 425 Union Center, Wichita, Kansas

Lease Name: Keeler Well No. # 1

Location: SE SW SW Sec. 17 Twp. 21 Rge. 11 (E) (W) W

County Stafford Total Depth 3490' Oil Well     

Gas Well      Input Well      SWD Well      D & A X Lost Hole     

Mr. Arnott was instructed to plug the well as follows:

260' of 8 5/8" surface pipe, cemented with 175 sacks. Fill hole with mud to 250', rock bridge from 250' to 240', and cement with 25 sacks. Fill hole with mud to 40', rock bridge from 40' to 30', and cement with 10 sacks to the base of the cellar.

Very truly yours,

Archie Elving  
Conservation Division Agent