

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

P. O. Box 17027 3830 S. Meridian
WICHITA, KANSAS 67217

December 28, 1974

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)RECEIVED
STATE CORPORATION COMMISSION

JAN 2 1974

CONSERVATION DIVISION
Wichita, KansasJ. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Harold Bergman of Bergman Oil Company has this

date requested permission to plug the following described well:

Mr. Bergman guarantees payment of the plugging fee.Operator's full Name: Bergman Oil CompanyComplete Address: 425 Union Center, Wichita, Kansas 67202Lease Name: Hitschmann "B" Well No. 1Location: 1980' North & 990' W SEC. 28 Twp. 16 Rge. 12 (E) (W) XCounty: Barton Total Depth 3394' Oil WellGas Well Input Well SWD Well D & A X Lost Hole Mr. Bergman was instructed to plug the well as follows:Fill hole with mud. Push plug to 500' and pump 40 sackscement through drill pipe at 500'. Pump 25 sacks cementthrough drill pipe at 290'. Push plug and $\frac{1}{2}$ sack hulls to40' and cap hole with 10 sacks cement. Bridge rathole andcement with 2 sacks cement.

Very truly yours,

Conservation Division Agent