

10-30-87 15.185.20208.0001

API NUMBER 15-185-20,208-A

1 120041

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

NE SW NE, SEC. 28, T 21 S, R 14 W/4  
3630 feet from S section line  
1650 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6588

Lease Name Smith (OWWO) Well # 1

Operator: Woodman-Iannitti  
Name & Address Box 308  
Great Bend, KS 67530

County Stafford 126.10  
Well Total Depth 3880 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8 feet 285

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Rockhold Engineering, Inc. License Number 5111

Address Box 698, Great Bend, KS 67530

Company to plug at: Hour: 10 a.m. Day: 30 Month: 10 Year: 19 87

Plugging proposal received from Deacon Pulley

(company name) Rockhold Engineering, Inc. (phone) 316-792-2506

were: 4 1/2" at 3865' PBD 3620' Perfs at 3556-76'

1st plug sand back to 3500' and dump 4 sx cement on top of sand through bailer,  
2nd plug pump 3 sx hulls, 20 sx cement, 5 sx gel and 90 sx econolite.

Plugging Proposal Received by Paul Luthi & James Kapp  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 11 a.m. Day: 30 Month: 10 Year: 19 87

ACTUAL PLUGGING REPORT 1st plug sanded back to 3500' and dumped 4 sx cement on top of  
sand through bailer,

2nd plug pumped into 8 5/8" surface casing with 300 lbs. hulls, 20 sx cement, 5 sx gel, released  
8 5/8" wiper plug and pumped 90 sx cement.

Remarks: Used Thrifty Mix cement by B.J. Titan. Recovered 2500' of 4 1/2" casing.

(If additional description is necessary, use BACK of this form.)

INVOICED RECEIVED  
I (and I observe this plugging) STATE CORPORATION COMMISSION

DATE 11-10-87  
INV. NO. 18781

NOV 5 1987 Signed Duane Rankin  
(TECHNICIAN)