

To: 1 051491  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

<sup>10-29</sup>  
API NUMBER 15- 185-22,749.0000 262  
330' E of C W/2, SEC. 28, T. 21 S, R 14 W/4E

TECHNICIAN'S PLUGGING REPORT

Operator License # 4384  
Operator: Hamp Oil Company  
Name & Address P.O. Box 391  
Ponca City, OK 74602

2640 feet from S section line  
3630 feet from E section line  
Lease Name Smith Well # 1  
County Stafford 123.37  
Well Total Depth 3796 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8 feet 332

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_  
Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Lyons Well Service License Number 30375  
Address 1103 S. St. John, Lyons, KS 67554

Company to plug at: Hour: 2 p.m. Day: 29 Month: 10 Year: 19 91

Plugging proposal received from Dewey Gressel  
(company name) Lyons Well Service (phone) 316-257-5524

were: 5 1/2" at 3795' w/175 sx cement, PBTD 3750', Perfs at 3590-94, 3702-14'  
1st plug sand back to 3540' and dump 5 sx cement on top of sand through bailer,  
2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8"  
wiper plug and pump 125 sx cement.

Plugging Proposal Received by Steve Pfeifer  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 3:05 p.m. Day: 29 Month: 10 Year: 19 91

ACTUAL PLUGGING REPORT 1st plug sanded back to 3540' and dumped 5 sx cement on top of sand  
through bailer,

2nd plug pumped 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8"  
wiper plug and pump 125 sx cement.

Maximum pressure 500 psi and shut in 300 psi.

RECEIVED  
STATE CORPORATION COMMISSION

NOV 4 1991

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 2040' of 5 1/2" casing.  
(If additional description is necessary, use BACK of this form.)

I (did/ did not) observe this plugging.

DATE 11-22-91

INV. NO. 333827

Signed Richard W. Tracy  
(TECHNICIAN)