

15.195.10812.0000

1 120322

10-11

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-Drill Completion Date 12/19/55
NW NW NW, SEC. 28, T 21 S, R 14 W/E

TECHNICIAN'S PLUGGING REPORT

4950 feet from S section line
4950 feet from E section line

Operator License # 5427

Lease Name Eva Smith Well # 1

Operator: D.R. Lauck Oil Company, Inc.
Name & Address 221 South Broadway, Suite 400
Wichita, KS 67202

County Stafford 123.24

Well Total Depth 3792 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 863

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Pulling License Number 6050

Address Box 347, Chase, KS 67524

Company to plug at: Hour: 1 p.m. Day: 11 Month: 10 Year: 19 89

Plugging proposal received from Millard Kelso

(company name) Kelso Casing Pulling (phone) 316-938-2457

were: 5 1/2" at 3816' PBD 3779' Perfs at 3749-64'

1st plug sand back to 3700' and dump 5 sx cement on top of sand through bailer,

2nd plug pump 4 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8"

wiper plug and pump 100 sx cement.

Plugging Proposal Received by Richard Lacey
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 2:45 p.m. Day: 11 Month: 10 Year: 19 89

ACTUAL PLUGGING REPORT 1st plug sanded 5 1/2" casing back to 3700' and dumped 5 sx cement on top of sand through bailer,

2nd plug pumped into 8 5/8" surface casing with 400 lbs. hulls, 15 sx gel, 50 sx cement, 5 sx gel, 100 lbs. hulls, released 8 5/8" wiper plug and pumped 100 sx cement.

Pumping pressure 1-1000 psi and shut in 800 psi.

RECEIVED
STATE CORPORATION COMMISSION

OCT 19 1989

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 2000' of 5 1/2" casing in CONSERVATION DIVISION
(If additional description is necessary, use BACK of this form.) Kansas

INVOICED

DATE 10-24-89

Signed Richard Rankin
(TECHNICIAN)

INV. NO. 26198