

1 080486

15.185.10808.0000

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- Comp. 5-14-51  
NW NW SE, SEC. 27, T 21 S, R 14 W/E

TECHNICIAN'S PLUGGING REPORT

2310 feet from S section line  
2310 feet from E section line

Operator License # 6568

Lease Name Pile Well # 2

Operator: Kaiser-Francis Oil Company  
Name & Address P. O. Box 21468  
Tulsa, OK 74121-1468

County Stafford 123.83

Well Total Depth 3810 feet

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet 435

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Rockhold Engineering, Inc. License Number 5111

Address P. O. Box 698, Great Bend, KS 67530

Company to plug at: Hour: 9:30 am Day: 7 Month: February Year: 19 86

Plugging proposal received from Deacon Pulley

(company name) Rockhold (phone) 316-792-2506

were: 5 1/2" at 3807' PBTD 3785' Perfs at 3572-3581'; 3530-3540'

1st plug sand back to 3480' and dump 5 sx cement on top of sand through bailer

2nd plug squeeze well with 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sack hulls,

release 8 5/8" rubber plug and pump 120 sx cement.

Plugging Proposal Received by Richard W. Lacey  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 10:30 am Day: 7 Month: February Year: 19 86

ACTUAL PLUGGING REPORT 1st plug sanded back to 3480' and dumped 5 sx cement on to p of sand through bailer, 2nd plug squeezed well with 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sack hulls, released 8 5/8" rubber plug and pumped 120 sx cement.

RECEIVED  
STATE CORPORATION COMMISSION

Maximum pressure 500 psi and shut in 200 psi

FEB 17 1986

Remarks: Recovered 2000' 5 1/2" casing. Used 60/40 Pozmix 6% gel loss prevention.  
(if additional description is necessary, use BACK of this Wichita, Kansas

INVOICED

observe this plugging.

DATE 1-17-86

Signed J. A. Melf  
(TECHNICIAN)

INV. NO. 12618