

1 120309

15.185.20579.0000
9-27

166 R

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- Docket #E-10,320

TECHNICIAN'S PLUGGING REPORT

S/2 SE NW, SEC. 27, T 21 S, R 14 W/E
2970 feet from S section line
3300 feet from E section line

Operator License # 6568

Lease Name Devine Well # 1

Operator: Kaiser-Frances Oil Company

County Stafford 120.51

Name & Address P.O. Box 21468

Well Total Depth 3708 feet

Tulsa, OK 74121-1468

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 280

Abandoned Oil Well Gas Well Input Well X SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Kelso Casing Pulling License Number 6050

Address Box 347, Chase, KS 67524

Company to plug at: Hour: 3 p.m. Day: 27 Month: 9 Year: 19 89

Plugging proposal received from Millard Kelso

(company name) Kelso Casing Pulling (phone) 316-938-2457

were: 5 1/2" at 3705' PBSD 3705' Perfs at 3544-48' Elevation 1936' KB

1st plug sand back to 3500' and dump 5 sx cement on top of sand through bailer,
2nd plug pump 4 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8"
wiper plug and pump 100 sx cement.

Plugging Proposal Received by Richard Lacey (TECHNICIAN)

Plugging Operations attended by Agent?: All X Part None

Operations Completed: Hour: 4 p.m. Day: 27 Month: 9 Year: 19 89

ACTUAL PLUGGING REPORT 1st plug sanded 5 1/2" casing back to 3490' and dumped 5 sx cement
on top of sand through bailer.

2nd plug pumped into 8 5/8" surface casing with 400 lbs. hulls, 10 sx gel, 50 sx cement,
10 sx gel, 100 lbs. hulls, released 8 5/8" wiper plug and pumped 100 sx cement.

Pumping pressure 0-600 psi and shut in 300 psi.

STATE CORPORATION COMMISSION

OCT 04 1989 10-4-89

Remarks: Used 60/40 Pozmix 6% gel by B.J. Titan. Recovered 2600 gals of 5 1/2" casing.
(If additional description is necessary, use BACK of this form.)

INVOICED

(If additional description is necessary, use BACK of this form.) observe this plugging.

DATE 10-9-89

Signed [Signature] (TECHNICIAN)

INV. NO. 26051