

1090356

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 083-21,146.0000 *R*

C SW NE, SEC. 22, T 21 S, R 23 W/EX  
3300 feet from S section line  
1980 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 9664

Lease Name Wellensiek Well # 1-22

Operator: Camco Energy, Inc.

County Hodgeman 149.50

Name & Address 243 Industrial

(Mississippi)  
Well Total Depth 4600 feet

Bedford, TX 76021

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 541

T/A WELL  
Abandoned Oil Well  Gas Well  Input Well  SWD Well  D&A

Other well as hereinafter indicated

Plugging Contractor Hembree Well Service, Inc. License Number 6907

Address Box 458, Ness City, KS 67560

Company to plug at: Hour: 6:30 pm Day: 17 Month: June Year: 19 85

Plugging proposal received from Darrell John

(company name) Hembree Well Service (phone) 913-798-3408

were: 4 1/2" at 4598' Perfs at 4558-64' 4196-4200'

1st plug sand back to 4500' and dump 4 sx cement on top of sand. Shoot off pipe and spot 25 sx cement.

2nd plug squeeze well with 3 sx hulls, 15 sx gel, 50 sx cement, 10 sx gel, 1 sack hulls, release 8 5/8" rubber plug and pump 150 sx cement.

Plugging Proposal Received by Robert B. Tarbutton (TECHNICIAN)

Plugging Operations attended by Agent?: All  Part  None

Operations Completed: Hour: 7:45 pm Day: 17 Month: June Year: 19 85

ACTUAL PLUGGING REPORT 1st plug sanded back to 4500' and dumped 4 sx cement on top of sand through bailer, shoot off pipe and spot 25 sx cement. 2nd plug squeezed well with 3 sx hulls, 15 sx gel, 50 sx cement, 10 sx gel, 1 sack hulls, released 8 5/8" rubber plug and pumped 150 sx cement.

RECEIVED  
STATE CORPORATION COMMISSION

Maximum pressure 400 psi and shut in 100 psi

6-21-1985 JUN 21 1985

Remarks: Used 60/40 Pozmix 6% gel by BJ-Titan.

CONSERVATION DIVISION

(If additional description is necessary, use BACK of this form.) Kansas

INVOICED

(If additional description is necessary, use BACK of this form.) observe this plugging.

DATE 6-24-85

Signed Robert B. Tarbutton (TECHNICIAN)

INV. NO. 8664 6-17