

1 060957

MAY 1 1 1987

API NUMBER 15-097-20,576-0000

C SE NE, SEC. 13, T 28 S, R 16 (W) (X)

3300 feet from S section line

660 feet from E section line

Lease Name Ross "C" Well # 1

County Kiowa 151.84

Well Total Depth 4672 feet

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet 413

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

TECHNICIAN'S PLUGGING REPORT

Operator License # 5171

Operator: TXO Production Corporation  
Name & Address 155 North Market, Suite 1000  
Wichita, KS 67202

Abandoned Oil Well \_\_\_\_\_ Gas Well X Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Hays Well Service License Number 5429

Address P.O. Box 108, Attica, KS

Company to plug at: Hour: 11:30 a.m. Day: 11 Month: 5 Year: 1987

Plugging proposal received from Vernon Schraut

(company name) TXO Production Corporation (phone) 316-269-7600

were: 4 1/2" at 4658' Perfs at 3457-63'

1st plug sand back to 3236' and dump 4 sx cement on top of sand through bailer,

2nd plug pump 3 sx hulls, 15 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8"

wiper plug and pump 100 sx cement.

Plugging Proposal Received by Paul Luthi  
(TECHNICIAN)

Plugging Operations attended by Agent?: All X Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 1:30 p.m. Day: 11 Month: 5 Year: 1987

ACTUAL PLUGGING REPORT 1st plug sanded back to 3236' and dumped 4 sx cement on top of sand through bailer,

2nd plug pumped 3 sx hulls, 15 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, released

8 5/8" wiper plug and pumped 100 sx cement.

Maximum pressure 500 psi and shut in 300 psi. Used 60/40 Pozmix 6% gel by B.J. Titan.

Remarks: Recovered 2500' of 4 1/2" casing.

(If additional description is necessary, use BACK of this form.)

STATE CORPORATION COMMISSION

**INVOICED**

(I did observe this plugging.)

Signed Paul A. Luthi  
(TECHNICIAN)

DATE 5-15-87

INV. NO. 15922