

1052258

TO: STATE CORPORATION COMMISSION

5-21

API NUMBER 15-145-21,125.0000  
NW NW NE , SEC. 6 , T 21 S, R 15 W

CONSERVATION DIVISION - PLUGGING SECTION 4950' FEET FROM SOUTH SECTION LINE

WICHITA STATE OFFICE BLDG., 130 S. MARKET 2310 FEET FROM EAST SECTION LINE

WICHITA, KANSAS 67202

1998 LEASE NAME MAUNY DIRKS WELL # 1

TECHNICIAN'S PLUGGING REPORT COUNTY PAWNEE

OPERATOR LICENSE # 3833 WELL TOTAL DEPTH 3853 125.23 FEET

OPERATOR: JOHN H. SHaida PRODUCTION CSG: SIZE 5 1/2" FEET 3886'

NAME AND ADDRESS 4126 N. SWEET BAY CIRCLE SURFACE CASING: SIZE 8 5/8" FEET 1004'

ADDRESS WICHITA, KS 67226

ABANDONED OIL WELL  GAS WELL  INPUT WELL  SWD WELL  D/A

OTHER WELL AS HEREINAFTER INDICATED

PLUGGING CONTRACTOR MIKES TESTING AND SALVAGE INC LICENSE NUMBER 31529

ADDRESS P. O. BOX 467, CHASE, KS 67524

COMPANY TO PLUG AT: HOUR: 12:00 AM DAY: 21 MONTH: MAY YEAR: 1998

PLUGGING PROPOSAL RECEIVED FROM MIKES KELSO

(COMPANY NAME) MIKES TESTING AND SALVAGE INC (PHONE) 316-938-2943

WERE: PERFORATIONS 3807'-3836'

SAND BOTTOM TO 3750' AND PLACE 5 SX OF CEMENT ON TOP OF THE SAND WITH DUMP BAILOR

5 1/2" WAS STUCK IN THE HOLE

FILL TOP 1000' OF 5 1/2" WITH CEMENT

PRESSURE TEST 8 5/8" X 5 1/2" ANNULAS WITH CEMENT.

RECOMMENDED 60/40 POZMIX 6% GEL PLUGGING PROPOSAL RECEIVED BY RICHARD LACEY

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL  PART  NONE

OPERATIONS COMPLETED: HOUR: 1:00 PM DAY: 21 MONTH: MAY YEAR: 1998

ACTUAL PLUGGING REPORT SANDED BOTTOM TO 3750' AND PLACED 5 SX OF CEMENT ON TOP OF SAND.

PUMPED 100 SX OF CEMENT DOWN THE 5 1/2" FILLING THE TOP 1000' OF CASING.

VISUALLY CHECKED SUFACE HEAD AND FOUND CEMENT

PUMPED 1/4 SX OF CEMENT DOWN THE 8 5/8" X 5 1/2" ANNULAS PRESSURING IT TO 500 PSIG

REMARKS: USED 60/40 POZMIX 6% GEL BY ALLIED RECOVERED 0000' OF 5 1/2" CASING  
(IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.)

I (BILL) RESERVE THIS PLUGGING.

SIGNED Richard W. Lacey  
(TECHNICIAN) FORM CP-2/3

DATE MAY 27 1998

INV. NO. 50633

INVOICED