

1 090096

7-3

135 R

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 145-21,366.0000

SW SW NE, SEC. 6, T 21 S, R 15 W/8  
2970 feet from S section line  
2310 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5418

Lease Name Mauney Dirks Well # 2-6

Operator: Allen Drilling Company  
Name & Address 7950 E. Prentice, Suite 100  
Englewood, CO 80111

County Pawnee 126.75

Well Total Depth 3900 feet

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet 966

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A X

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Allen Drilling Company License Number 5418

Address 7950 E. Prentice, Suite 100, Englewood, CO 80111

Company to plug at: Hour: 6 a.m. Day: 3 Month: 7 Year: 19 91

Plugging proposal received from John Johnson

(company name) Allen Drilling Company (phone) 303-796-7350

were: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 955'

1st plug at Arbuckle with 40 sx cement, 2nd plug at 975' with 50 sx cement,

3rd plug at 480' with 50 sx cement,

4th plug at 40' with 10 sx cement,

5th plug to circulate rathole with 15 sx cement.

Plugging Proposal Received by Steve Middleton (TECHNICIAN)

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part \_\_\_\_\_ None X

Operations Completed: Hour: 12:30 p. May: 3 Month: 7 Year: 19 91

ACTUAL PLUGGING REPORT 1st plug at 3840' with 40 sx cement,

2nd plug at 975' with 50 sx cement,

3rd plug at 480' with 50 sx cement,

4th plug at 40' with 10 sx cement,

5th plug to circulate rathole with 15 sx cement.

Remarks: Used 60/40 Pozmix 6% gel by Halliburton.

(if additional description is necessary, use BACK of this form.)

RECEIVED STATE CORPORATION COMMISSION

JUL 09 1991

CONSERVATION DIVISION Wichita, Kansas

INVOICED (if not) observe this plugging.

Signed [Signature] (TECHNICIAN)

DATE JUL 19 1991

INV. NO. 32322

7-3

15.145.21366.0000

EFFECTIVE DATE: 5-26-91

FORM MUST BE TYPED  
FORM C-1 4/90

State of Kansas

FORM MUST BE SIGNED  
ALL BLANKS MUST BE FILLED

NOTICE OF INTENTION TO DRILL 145-21366  
Must be approved by the K.C.C. five (5) days prior to commencing well

Expected Spud Date May 30, 1991  
month day year

..SW ..SW ..NE. Sec ..6.. Twp ..21. s, Rg ..15 X East West

OPERATOR: License # 5418  
Name: Allen Drilling Company  
Address: 7950 E. Prentice - Suite 100  
City/State/Zip: Englewood, Colorado 80111  
Contact Person: Doug Hoisington  
Phone: (303) 796-7350

..... 2970' ..... feet from South line of Section  
..... 2310' ..... feet from East line of Section  
(Note: Locate well on Section Plat on Reverse Side)

CONTRACTOR: License #: 5418  
Name: Allen Drilling Company

County: Pawnee  
Lease Name: Mauney Dirks Well #: 2-6  
Field Name: Pawnee Rock

Well Drilled For: Well Class: Type Equipment:  
X Oil ... Inj ... Infield X Mud Rotary  
... Gas ... Storage X Pool Ext. ... Air Rotary  
... OGW/O ... Disposal ... Wildcat ... Cable  
... Seismic; ... # of Holes

Is this a Prorated Field? ... yes X no  
Target Formation(s): Arbuckle  
Nearest lease or unit boundary: 330'  
Ground Surface Elevation: 1959' feet MSL  
Domestic well within 330 feet: X yes ... no  
Municipal well within one mile: ... yes X no  
Depth to bottom of fresh water: 140'  
Depth to bottom of usable water: 230'  
Surface Pipe by Alternate: X 1 ... 2  
Length of Surface Pipe Planned to be set: 1020'  
Length of Conductor pipe required: N/A  
Projected Total Depth: 3900'  
Formation at Total Depth: Arbuckle  
Water Source for Drilling Operations:  
..... well ..... farm pond X other

If OGW/O: old well information as follows:  
Operator: N/A  
Well Name: \_\_\_\_\_  
Comp. Date: \_\_\_\_\_ Old Total Depth \_\_\_\_\_

RECEIVED  
STATE BOREHOLE INFORMATION COMMISSION  
Will Cores Be Taken?: ... yes X no  
If \_\_\_\_\_ cores are \_\_\_\_\_

Directional, Deviated or Horizontal wellbore? ... yes X no  
If yes, total depth location: \_\_\_\_\_

AFFIDAVIT CONSERVATION DIVISION  
Wichita, Kansas

The undersigned hereby affirms that the drilling, completion and eventual plugging of this well will comply with K.S.A. 55-101, et. seq.  
It is agreed that the following minimum requirements will be met:

Pusher John Johnson  
SPUD DATE 6-27-91 INIT. Alles

LENGTH SURFACE PLANNED 910'  
RESERVE PIT STATUS- REMOVE FLUID \_\_\_\_\_ LINED \_\_\_\_\_  
after salt sect. \_\_\_\_\_ bbls. \_\_\_\_\_ when done \_\_\_\_\_ bbls.

RATHOLED AHEAD? Y N SIZE HOLE \_\_\_\_\_  
SURFACE PIPE 8 5/8" @ 966' CONDUCTOR \_\_\_\_\_  
ANHYDRITE T- 958 B- \_\_\_\_\_ ELEVATION \_\_\_\_\_

TD 3900 FORMATION Arbuckle

RAN PIPE @ \_\_\_\_\_ DV TOOL \_\_\_\_\_ ALT II DONE \_\_\_\_\_  
\_\_\_\_\_ SX \_\_\_\_\_ SX Y \_\_\_\_\_ N

3280 Arbuckle Plug @ 2840 Ft. w/ 40 SX

\_\_\_\_\_ Hug./Council @ \_\_\_\_\_ Ft. w/ \_\_\_\_\_ SX

\_\_\_\_\_ Anhydrite Base @ 775 Ft. w/ 50 SX

\_\_\_\_\_ 1/2 Base Anyh. @ 480 Ft. w/ 50 SX

\_\_\_\_\_ 1/2, 1/2 Plug @ \_\_\_\_\_ Ft. w/ \_\_\_\_\_ SX

\_\_\_\_\_ Bottom Surface @ \_\_\_\_\_ Ft. w/ \_\_\_\_\_ SX

\_\_\_\_\_ 40' Plug @ 40 Ft. w/ 10 SX

RAT HOLE CIRC/W 19 SX MOUSE HOLE W/ \_\_\_\_\_ SX

WATER WELL \_\_\_\_\_ SX (Irr. Well \_\_\_\_\_ Pond \_\_\_\_\_)  
TECHNICIAN Sm DATE 7-1-91 Hauling \_\_\_\_\_

TYPE OF CEMENT 60/40 672

STARTING TIME 6:00 (AM/PM) DATE 7-3-91

COMPLETION TIME 12:30 (AM/PM) DATE 7-3-91

EMENT COMPANY HILLIBURTOR