

1090208

15.185.20170.0000

API NUMBER 15-047-20,704

STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

SE NE NW, SEC. 17, T 21 S, R 11 ~~WXX~~
4290 feet from ~~NXX~~ SE Corner of
W SE Corner of
2310 feet from ~~WXX~~ section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5056

Lease Name Keeler Well # 1-17 SWD

Operator: F. G. Holl

County Stafford

Name & Address 6427 East Kellogg

Well Total Depth 4470 145.28 feet

Wichita, KS 67208

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 250

Abandoned Oil Well Gas Well Input Well SWD Well X D&A

Other well as hereinafter indicated

Plugging Contractor Kelso Casing Pulling License Number 6050

Address Box 347, Chase, KS 67524

Company to plug at: Hour: 11:30 am Day: 27 Month: July Year: 19 84

Plugging proposal received from Mike Gomez

(company name) Kelso (phone) 316-938-2457

were: 4 1/2" parted at 1000' - could not pull pipe and recovered only 12' of 4 1/2" 4 1/2" at 3500' Perfs at 3418-3455' PBSD 3532

plug well with 150 sx 50/50 Pozmix with 2% gel 3% CaCl then follow with 100 sx 60/40 Pozmix with 2% gel 3% CC.

Plugging Proposal Received by R. Barlett (TECHNICIAN)

Plugging Operations attended by Agent?: All X Part None

Operations Completed: Hour: 1:00 pm Day: 27 Month: July Year: 19 84

ACTUAL PLUGGING REPORT 4 1/2" at 3500' Perfs at 3418-3455' PBSD 3532'

4 1/2" parted at 1000' - could not pull pipe and recovered only 12' of 4 1/2" casing.

Plugged well with 150 sx 50/50 Pozmix 2% gel 3% CaCl then followed with 100 sx 60/40 Pozmix 2% gel 3% CaCl.

RECEIVED STATE CORPORATION COMMISSION

AUG 01 1984

Remarks: Recovered 12' of 4 1/2" casing, by Allied No. 37471

If additional description is necessary, use BACK of this

CONSERVATION DIVISION Wichita, Kansas

INVOICED

DATE 8-3-84 observe this plugging.

Signed R. Barlett (TECHNICIAN)

INV. NO. 2851