

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-185-20247-00-00
Spot: CNESWNE Sec/Twnshp/Rge: 17-21S-11W
3630 feet from S Section Line, 1650 feet from E Section Line
Lease/Unit Name: SMITH EST Well Number: 4
County: STAFFORD Total Vertical Depth: 3445 feet

Operator License No.: 5056
Op Name: HOLL, F.G., COMPANY L.L.C.
Address: 6427 EAST KELLOGG
WICHITA, KS 67207

Conductor Pipe: Size feet: \$111.96
Surface Casing: Size 8.625 feet: 250 WITH 225 SX CMT
Production: Size 4.5 feet: 3440 WITH 150 SX CMT
Liner: Size feet:

Well Type: OIL UIC Docket No: Date/Time to Plug: 03/14/2002 2:30 PM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: ROB LONG Company: F.G. HOLL Phone: (316) 684-8481

Proposed Plugging Method: SAND TO 3320' & 4 SX CMT. PLUG AT 600' WITH 10 SX GEL - 50 SX CMT. PLUG AT 280' WITH 50 SX CMT. PLUG AT 40' WITH 10 SX CMT OR PUMP 300# HULLS - 10 SX GEL - 50 SX CMT - 10 SX GEL - 100# HULLS - 8 5/8" PLUG - 100 SX CMT.

Plugging Proposal Received By: RICHARD LACEY WitnessType: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 03/14/2002 3:25 PM KCC Agent: RICHARD LACEY

Actual Plugging Report:

PBTD 3440'. PERFS AT 3390-3400 & 3376-3380'. SANDED TO 3220' & 4 SX CMT ON TOP WITH DUMP BAILER. PULLED CASING & PUMPED PLUGS DOWN 8 5/8" WITH 300# HULLS - 10 SX GEL - 50 SX CMT - 10 SX GEL - 100# HULLS - RELEASED 8 5/8" PLUG - 100 SX CMT. MAXIMUM PRESSURE 600 PSIG. SHUT IN PRESSURE 200 PSIG.

RECEIVED
APR 01 2002
KCC WICHITA

Remarks: USED 60/40 POZMIX 6% GEL BY ACID SERVICES. RECOVERED 1600' OF 4 1/2" CASING.

Plugged through: CSG

District: 01

Signed Richard M. Lacey
(TECHNICIAN)

INVOICED
DATE 4-2-02
WV. NO. 2002061599

MAR 20 2002

Form 1-23