

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-159-22717-01-00
Spot: NWNESENE Sec/Twnshp/Rge: 19-21S-6W
1460 feet from N Section Line, 440 feet from E Section Line
Lease Name: HEDRICK 2106 Well #: 19-1H
County: RICE Total Vertical Depth: 7285 feet

Operator License No.: 35053
Op Name: TAPSTONE ENERGY, LLC
Address: PO BOX 1608
OKLAHOMA CITY, OK 73101

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP	7	3160		
COND	18	63		22 sx cement
	11	7		375 sx cement
L1	4.5	7270		280 sx cement
PROD	4.5	7270		280 SX
SURF	9.625	376		270 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 06/30/2017 8:30 AM
Plug Co. License No.: 35086 Plug Co. Name: SJL WELL SERVICE, LLC
Proposal Rcvd. from: BOONE DAVIDSON Company: TAPSTONE ENERGY, LLC Phone: (580) 554-8277

Proposed Plugging Method: MIRU, SET CIBP AT 3170' AND CAP WITH 25 SX'S COMMON CEMENT. CUT 7', PULL OUT AND RUN TUBING TO 1150'. PUMP 100 SX'S AND TAG. CIRCULATE FROM 450' TO SURFACE THRU TUBING, PULL OUT TUBING AND TOP OFF.

Plugging Proposal Received By: VIRGIL CLOTHIER WitnessType: PARTIAL
Date/Time Plugging Completed: 06/30/2017 11:00 AM KCC Agent: VIRGIL CLOTHIER

Actual Plugging Report:

Perfs:

MIRU, SET CIBP AT 3160'. RUN CEMENT BOND LOG TO DETERMINE TOC, FOUND TO BE ALL THE WAY UP TO SURFACE. RUN TUBING TO 3140' AND PUMP 25 SX'S COMMON CEMENT. PULL TUBING TO 1150' AND PUMPED 235 SX'S CEMENT AND CIRCULATED CEMENT TO SURFACE. PULL TUBING OUT AND TOP OFF. TOPPED OFF RAT HOLE ALSO. CUT OFF WELL-HEAD AND WELDED PLATE ON TOP OF CASING THAT LABELED WELL.

INVOICED
AUG 29 2017

Remarks: BASIC SERVICE'S #15125. ELI WIRELINE #1194. THIS WAS A TA'D WELL APPROVED TILL 9-8-2017

Plugged through: TBG

District: 02

Signed Virgil Clothier
(TECHNICIAN)

JK