

TO:

STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-073-01408-00-00

Spot: NENENW

Sec/Twnshp/Rge: 16-23S-13E

4950 feet from S Section Line, 2970 feet from E Section Line

Lease Name: SCHINDLER

Well #: 3

County: GREENWOOD

Total Vertical Depth: 1802 feet

Operator License No.: 32044

Op Name: TRIMBLE & MACLASKEY OIL LLC

Address: 110 SOUTH ST PO BOX 171
GRIDLEY, KS 66852

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	1782		30 SX
SURF	8.625	20		5 SX

Well Type: OIL

UIC Docket No:

Date/Time to Plug: 08/02/2017 9:00 AM

Plug Co. License No.: 32044

Plug Co. Name: TRIMBLE & MACLASKEY OIL LLC

Proposal Rcvd. from: JIM THWEATT

Company:

Phone: (620) 836-2000

Proposed
Plugging
Method:

Cement plug on bottom, perf at 850ft and 250ft, cement plug at 850ft and cement at 250ft to surface

Plugging Proposal Received By: MICHAEL HEFFERN

WitnessType: COMPLETE (100%)

Date/Time Plugging Completed: 08/02/2017 12:00 PM

KCC Agent: MICHAEL HEFFERN

Actual Plugging Report:

Perfs:

ran tubing to 1701', pumped 20 sxs cement, pulled tubing to 862', pumped 15 sxs cement, pulled tubing to 250', pumped 95 sxs cement to surface, gel spacers between cement plugs.

RECEIVED
KCC DIST #3
AUG 14 2017
CHANUTE, KS

MH


INVOICED
AUG 29 2017

Remarks:

Plugged through: TBG

District: 03

Signed



(TECHNICIAN)

810 E 7TH
 PO Box 92
 EUREKA, KS 67045
 (620) 583-5561



15-073-01408-0000

Cement or Acid Field Report
 Ticket No. **3452**
 Foreman Rick Ledford
 Camp Eureka Ks

Date	Cust. ID #	Lease & Well Number	Section	Township	Range	County	State
8-2-17	1200	Schindler # 3	11e	23s	13E	GW	Ks
Customer			Unit #	Driver	Unit #	Driver	
Trimble + Macloskey Oil LLC			102	Rick L.			
Mailing Address			112	Jason H.			
P.O. Box 171			121	Steve M.			
City			125	Chris M.			
State		Zip Code					
Ks		66852					

Job Type P.T.A. Hole Depth _____ Slurry Vol. _____ Tubing 2 3/8"
 Casing Depth 1782' Hole Size _____ Slurry Wt. 14.8" Drill Pipe _____
 Casing Size & Wt. 5 1/2" Cement Left in Casing _____ Water Gal/SK 70 Other _____
 Displacement _____ Displacement PSI _____ Bump Plug to _____ BPM _____

Remarks: Safety meeting. Well perforated @ 250' - 252'
20 sks @ 1701'
Gel spacer
15 sks @ 862'
Gel spacer
95 sks @ 250' to surface
 "Thank You"

Code	Qty or Units	Description of Product or Services	Unit Price	Total
C105	1	Pump Charge	750.00	750.00
C107	30	Mileage	3.95	118.50
C203	130 sks	60/40 Perm cement	12.75	1657.50
C206	450"	4 7/8 gel	.20	90.00
C206	300"	gel-spacer	.20	60.00
C214	40"	hulls	.45	18.00
C102A	5.6	tan mileage bulk tank	m/c	345.00
C113	3 hrs	80 Bbl VAC TRK	85.00	255.00
C224	3000 gals	city water	10.00/1000	30.00
			Subtotal	3324.00
			Sales Tax	

Authorization by Brian Macloskey Title _____ Total _____

I agree to the payment terms and conditions of services provided on the back of this job ticket. Any amendments to payment terms must be in writing on the front of this job ticket or in the Customer's records at ELITE's office.