

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-155-21157-00-00  
Spot: NESW Sec/Twnshp/Rge: 16-25S-9W  
1980 feet from S Section Line, 3300 feet from E Section Line  
Lease Name: MAXWELL A Well #: 3  
County: RENO Total Vertical Depth: 3980 feet

Operator License No.: 33596  
Op Name: UNIT PETROLEUM COMPANY  
Address: 8200 SOUTH UNIT DRIVE  
TULSA, OK 74132

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3982	1500	150 SX
SURF	8.625	187		120 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 05/17/2017 12:00 AM  
Plug Co. License No.: 33338 Plug Co. Name: ORR ENTERPRISES, INC.  
Proposal Rcvd. from: RONNY ORR Company: ORR ENTERPRISES, INC. Phone: (918) 477-4510

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: VIRGIL CLOTHIER WitnessType: PARTIAL  
Date/Time Plugging Completed: 05/19/2017 4:00 PM KCC Agent: B. J. HOPE

Actual Plugging Report:

RUN IN WITH WIRE LINE & SET 5 1/2" CEMENT RETAINER @ 2800'. PICK UP TUBING & STINGER & STING INTO RETAINER - CHECK INJECTION RATE @ 3 BPM AT 900 PSI. STING OUT AND CIRCULATE HOLE, WITH 60 BBLS MUD, STING INTO RETAINER AND MIX & PUMP 125 SX CEMENT - STING OUT AND CAP CEMENT RETAINER W/10 SX CEMENT. WIRELINE CUT 5 1/2" CASING @ 1500'. LAYED DOWN 48 JTS OF 5 1/2" CASING. TIH W/TBG TO 1400' SPOTTED 35 SX CEMENT. TAGGED TOC @ 1134', PULL UP HOLE TO 800' AND SPOTTED 35 SX CEMENT. PULL UP HOLE TO 250' AND CIRCULATE CEMENT TO SURFACE W/ 75 SX CEMENT.

Perfs:

Top	Bot	Thru	Comments
3857	3870		

Remarks: CLASS A CEMENT USED, 10 YEAR TA, WITH JUNK IN HOLE.

Plugged through: TBG

District: 02

Signed

*B. J. Hope*

(TECHNICIAN)

INVOICED  
AUG 29 2017

18