

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-007-22222-00-00
Spot: E2W2SWNW Sec/Twnshp/Rge: 8-35S-13W
3313 feet from S Section Line, 4669 feet from E Section Line
Lease Name: STERNBERGER Well #: A-1
County: BARBER Total Vertical Depth: 4964 feet

Operator License No.: <u>33168</u>	String	Size	Depth (ft)	Pulled (ft)	Comments
Op Name: <u>WOOLSEY OPERATING COMPANY, LL</u>	CIBP	2.375	4830		WITH 2 SX CMT
Address: <u>125 N MARKET STE 1000</u>	PROD	4.5	4963	2020	WITH 100 SX CMT
<u>WICHITA, KS 67202</u>	SURF	8.625	383		WITH 300 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 07/11/2017 9:30 AM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: DAVID BRADY Company: QUALITY WELL SERVICE, INC. Phone: (620) 727-3410

Proposed Plugging Method: SET CIBP @ 4830' WITH 2 SX CMT. PLUG AT 700' WITH 10 SX GEL & 50 SX CMT. PLUG AT 400' WITH 50 SX CMT. PLUG AT 40' WITH 20 SX CMT.

Plugging Proposal Received By: STEVE PFEIFER WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 07/11/2017 11:30 PM KCC Agent: STEVE PFEIFER

Actual Plugging Report:

Perfs:

SET CIBP @ 4830' & PUT 2 SX CMT ON TOP OF CIBP THROUGH DUMP BAILER. 1ST PLUG AT 720' WITH 10 SX GEL & 50 SX CMT. 2ND PLUG AT 400' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 35 SX CMT.

Top	Bot	Thru	Comments
4928	4940		
4906	4916		
4883	4889		

Remarks: USED 60/40 POZMIX 4% GEL BY QUALITY WELL SERVICE.

INVOICED
AUG 30 2017

Plugged through: CSG

District: 01

Signed Stephan J Pfeifer
(TECHNICIAN)

RECEIVED
JUL 17 2017
KCC DODGE CITY