

5-16

4-060528

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API number: 15-009-21,373-00-00

C NW SW /4 SEC. 28, 16 S, 12 W
1980 feet from S section line
4620 feet from E section line

Operator license# 3682

Lease Finger well # 1

Operator: Mark Connell

County Barton

Address: R.R. 1 - Box 119
Claflin, Kansas 67525

Well total depth 3369 feet 109.49
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 215 feet

Aband. oil well X, Gas well , Input well , SWD , D & A

Plugging contractor: D.S. & W. Well Servicing, Inc. License# 6901

Address: P.O. Box 231 - Claflin, Kansas 67525

Company to plug at: Hour: 10:00A.M. Day: 16 Month: May Year: 94

Plugging proposal received from: Joe Strube

Company: D.S. & W. Well Servicing, Inc. Phone: 316-587-3361

Were: Order 175 sxs. 60/40 posmix - 10% gel and hulls.
Plug while pulling casing.

Plugging Proposal Received by: Herb Deines
Plugging operations attended by agent? All[X], Part[], None[]

Completed: Hour: 11:15A.M., Day: 16, Month: May, Year: 94

Actual plugging report: 8 5/8" to 215'. 4 1/2" to 3363' with 100 sxs.
Sanded back to 3300' and spotted 4 sxs. cement with dump bailer. Cut
casing at 2000' and pulled to 1575'. Mixed and pumped 75 sxs. cement
with 200# hulls. Pulled casing to 775' and pumped 35 sxs. with 100#
hulls. Pulled casing to 250' and circulated cement with 40 sxs.
Pulled casing with cement in cellar.

RECEIVED
STATE CORPORATION COMMISSION

MAY 25 1994

Remarks: Allied Cementing.
Condition of casing(in hole): GOOD X BAD Anhy. plug: YES X NO
Bottom plug(in place): YES X, CALC , NO Dakota plug: YES X, NO
Plugged through TUBING , CASING X. Elevation: 1915 GL

CONSERVATION DIVISION
Wichita, Kansas

I did not observe the plugging.

Herb Deines
DH (agent)

INVOICED
DATE 5-26-94
INV. NO. 40491