


STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Barton County, Sec. 28 Twp. 16 Rge. 12 (XX) (W)
Location as "NE/CNW/SW" or footage from lines SE-SW-SW
Lease Owner H. C. Bennett
Lease Name Finger Well No. 3
Office Address 1212 Union Nat'l Bldg., Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Oil Well
Date well completed 12-24-48 19____
Application for plugging filed 4-80-64 19____
Application for plugging approved _____ 19____
Plugging commenced 5-7--64 19____
Plugging completed 5-14-64 19____
Reason for abandonment of well or producing formation Depleted

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Donald Tryan
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3353 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	175'	None
				5 1/2"	3347'	1160.38'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Set rock bridge at 3085' and dumped 5 sax of cement.
Globe Cementing Co. pumped 80 sax of cement and 16 sax
mud down 8 5/8". Top of cement at 70'. Mudded hole to 12',
dumped 3-sax of cement. Filled to surface with dirt.

RECEIVED
STATE CORPORATION COMMISSION

JUN 8 1964

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Flint Engineering and Const. Co.
Address Box 950, El Dorado, Kansas

STATE OF Kansas, COUNTY OF Butler, ss.
Kenneth Smith (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Kenneth Smith
2375 West Central, El Dorado.
(Address)

SUBSCRIBED AND SWORN TO before me this 4 day of JUNE, 1964.

My commission expires Sept. 23, 1967

Ronald R. Hanson
Notary Public.

Top of Perforation

2095

15-009-07153-00-00

Lease Finger Well # 3 Pool Beaver South
Elevation 1896 RB Completed 12/24/48 28-16-12W
Initial Producing Horizon Arbuckle Log SE-SW-SW
Barton County

FORMATION TOPS:

	<u>Depth</u>	<u>Datum</u>	<u>Log</u>	<u>Shows of Oil or Gas and Zones that should be tested.</u>
Anhydrite	<u>795</u>	<u>±1101</u>		
Topeka				
Heebner	<u>2991</u>	<u>-1095</u>		
Brown Lims	<u>3080</u>	<u>-1184</u>		
Lansing	<u>3100</u>	<u>-1204</u>		
Mississippi				
Viola				
Simpson				
Conglomerate				
Arbuckle	<u>3346</u>	<u>-1450</u>		

Shows of Oil or Gas and Zones that should be tested.

No shows reported, but there are probably productive L-KC zones in this well. Porosity zones reported: 3143-47 in 43' 3184-95 in 86' 3227-31 in 129'

Other zones probably exist near top of Lansing.

Rotary Total Depth 3351 -1455
1st Deepening TD 3353 -1457
2nd Deepening TD _____
Plugged back to _____
Plugged back to _____

RECEIVED
STATE CORPORATION COMMISSION

JUN 8 1964

CONSERVATION DIVISION
Wichita, Kansas

CASING RECORD:

Surface Pipe 175 feet of 8 5/8" Cemented w/ 125 SK
Production Pipe 3347 feet of 5 1/2" Cemented w/ 100 SK
Liner _____ feet of _____ Cemented w/ _____ SK
Other _____ feet of _____ Cemented w/ _____ SK

Pipe 1' in Arbuckle - 6 feet of open hole.

plug for H C Bennett

Bridge plug at 3260

125 bbl. of oil in Tank + gun bbl. if need to spot oil
and if need more water - call water truck out of Brauer
Troy knows who to call

should get 2200 revs. if don't spot oil

Harrington - east to Redwing - no $7\frac{1}{2}$ mi + on east
side rd.

Ronald Inman Russell Hs. HU 3-3039