

9

15-009-07406-00-00


STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Barton County, Sec. 28 Twp. 16 Rge. 12 (E) (W)
SW NE NW

Location as "NE/CNWESW" or footage from lines
Lease Owner Morgenstern Oil Operations
Lease Name Laudick A#2 Well No. _____
Office Address Wichita, Kansas 67202
Character of Well (completed as Oil, Gas or Dry Hole) _____
Date well completed _____ 19____
Application for plugging filed _____ 19____
Application for plugging approved _____ 19____
Plugging commenced 12/18/71 _____ 19____
Plugging completed 12/23/71 _____ 19____
Reason for abandonment of well or producing formation depleted.
If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Truan
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3378 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8	325	none
				5 1/2"	3370	2320'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Checked hole to 3378', ran sand to 3350' and ran 5 sacks of cement.
Shot pipe at 2875', 2782', lost wire line in hole, fished line,
worked pipe loose and pulled 71 joints. Allied pumped 20 sacks
gel and 100 sacks of cement.

PLUGGING COMPLETE.

RECEIVED
STATE CORPORATION COMMISSION
JAN 17 1972
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor KNIGHT CASING PULLING CO., INC.
Address CHASE, KANSAS

STATE OF KANSAS, COUNTY OF RICE, ss.
NOEL J. KNIGHT (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Noel Knight
CHASE, KANSAS
(Address)

SUBSCRIBED AND SWORN TO before me this 30th day of December, 19 71
MARGARET MELCHER
NOTARY PUBLIC
Rice County, Kansas
My Commission Expires Feb. 15, 1975

Margaret Melcher
Notary Public.

WELL-LOG

Date Started: January 16, 1958
Date Completed: January 26, 1958

Laudick No. 2
SW NE NW
Section 28-16-12
Barton County, Kansas

Elevation	1918'	K.B.
Anhydrite	806'	
Heebner	3007'	(-1089)
Toronto	3023'	(-1105)
Douglas	3036'	(-1118)
Lansing	3113'	(-1195)
Conglomerate	3350'	(-1432)
Arbuckle	3364'	(-1446)
R.T.D.	3378'	(-1460)

8 5/8" set at 325'
5 1/2" set at 3370'

0'	-	70'	Surface Clay and Sand
70'	-	85'	Shale
85'	-	100'	Sand
100'	-	140'	Shale
140'	-	190'	Sand
190'	-	250'	Shale and Sand Streak
250'	-	275'	Sand
275'	-	325'	Shale
325'	-	400'	Shale
400'	-	410'	Sand
410'	-	420'	Shale
420'	-	425'	Sand
425'	-	465'	Shale
465'	-	470'	Sand
470'	-	493'	Shale
493'	-	496'	Very Hard Sand
496'	-	530'	Shale
530'	-	550'	Shale
550'	-	806'	Red Bed
806'	-	841'	Anhydrite
841'	-	1215'	Shell and Shale
1215'	-	1480'	Salt and Shale
1480'	-	1515'	Shale and Shell
1515'	-	1650'	Lime and Shale
1650'	-	1830'	Lime and Shale
1830'	-	1838'	Sand
1838'	-	1868'	Lime and Shale
1868'	-	1878'	Sharp Sand
1878'	-	2090'	Lime and Shale
2090'	-	2545'	Lime and Shale
2545'	-	2631'	Lime and Shale
2631'	-	2740'	Lime
2740'	-	2825'	Lime and Shale
2825'	-	2890'	Lime and Shale
2890'	-	2995'	Lime
2995'	-	3007'	Lime
3007'	-	3100'	Heebner
3100'	-	3113'	Lime
3113'	-	3290'	Lansing
3290'	-	3364'	Lime
3364'	-	3378'	Arbuckle
3378'	-		R.T.D.

RECEIVED
STATE CORPORATION COMMISSION
DEC 17 1971
CONSERVATION DIVISION
Wichita, Kansas

AFFIDAVIT

State of Kansas County of Barton
I, Cecil M. Olson, employee of the owner, do swear that the
statements and matter herein contained are true to the best of my knowledge.

THE DUKE DRILLING COMPANY

Subscribed and sworn before me this 12th day of February, 1958.

BY: Cecil Olson
John E. Stinson
NOTARY PUBLIC

My commission expires: June 24, 1959.