


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

Barton County. Sec. 30 Twp. 16 Rge. 12 (E) (W)
Location as "NE/CNW/SW" or footage from lines NW SW SW
Lease Owner Robert G. Brooks
Lease Name Reif Well No. 1
Office Address 102 G Insurance Bldg., Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed August 30 1967
Application for plugging filed August 30 1967
Application for plugging approved August 30 1967
Plugging commenced August 30 1967
Plugging completed August 30 1967
Reason for abandonment of well or producing formation Dry Hole



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Don Truan
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3420 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled hole with heavy mud to 425'. Set plug and hulls and 25 sacks of cement through drill pipe.

Filled hole to 300' and set plug and hulls and 25 sacks of cement through drill pipe.

Filled hole to 40' and put in 10 sacks of cement.

Put two sacks of cement in rat hole.

SEP 21 1967
CONSERVATION DIVISION
WICHITA, KANSAS
9-21-67

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Burt Drilling Co.
Address 1823 Washington, Great Bend, Kansas 67530


STATE OF KANSAS COUNTY OF BARTON, ss.
Duke C. Burt (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Duke C. Burt
1823 Washington, Great Bend, Kansas
(Address)

SUBSCRIBED AND SWORN to before me this 11th day of September, 19 67

Dexter Miner
Dexter Miner Notary Public.

My commission expires Oct. 15, 1967



ROBERT G. BROOKS
102 G Insurance Bldg.
Wichita, Kansas

Well: Reif No. 1
Commenced R.D.: 8-22-67
Completed R.D.: 8-30-67
Total Depth: 3420' D. F.
Casing: 312' of 8 5/8" 24# 8rd.thd.
Surface Pipe.

Sec.: 30-16-12
Barton County, Kansas
Elevation:
Initial Prod.: D & A
Contractor: BURT DRILLING
COMPANY

Strata	Depth
Post Rock	0- 103'
Shale & Shells	103- 310
Shale	310- 515
Redbed	515- 847
Anhydrite	847- 876
Shale & Shells	876-1530
Lime & Shale Streaks	1530-1620
Shale & Lime	1620-1850
Lime & Shale Streaks	1850-2020
Shale & Lime Streaks	2020-2305
Lime & Shale	2305-2600
Shale & Lime Streaks	2600-2767
Lime & Shale Streaks	2767-2890
Lime	2890-3046
Heebner Shale	3046-3050
Lime	3050-3074
Shale & Sand (Douglas)	3074-3130
Lime	3130-3382
Conglomerate	3382-3398
Lime (Arbuckle)	3398-3420

RECEIVED
STATE CORPORATION COMMISSION
SEP 21 1967

CONSERVATION DIVISION
Wichita, Kansas

I hereby certify that the above is a true and correct log of said well as reflected by daily reports.

BURT DRILLING CO.



Signed and sworn in my presence this 1st day of September, 1967.



Dexter Miner



My Commission Expires: Oct. 15, 1967