

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202

Barton County. Sec. 30 Twp. 16 Rge. 12 E/W
Location as "NE/CNW $\frac{1}{2}$ SW $\frac{1}{2}$ " or footage from lines _____

_____ NW NW NW
Lease Owner The Tipton Corp.

Lease Name Woydziak Well No. 1

Office Address Box 157, Hays, KS 67601

Character of Well (Completed as Oil, Gas or Dry Hole) _____
Dry hole

Date Well completed 10-6-1980

Application for plugging filed 10-6-1980

Application for plugging approved 10-6-1980

Plugging commenced 10-6-1980

Plugging completed 10-6-1980

Reason for abandonment of well or producing formation _____
Dry hole

If a producing well is abandoned, date of last production _____
_____ 19 _____

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Duane Rankin

Producing formation _____ Depth to top --- Bottom --- Total Depth of Well 3423'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	276'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Mud to 480' w/50 sks 50/50 Pozmix 4% Gel

Mud to 270' w/30 sks

Mud to 40' w/ $\frac{1}{2}$ sks hulls & 10 sks

5 sks in rathole

RECEIVED
STATE CORPORATION COMMISSION

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor _____

CONSERVATION DIVISION
Wichita, Kansas

STATE OF Kansas COUNTY OF Barton, ss.
Larry Curtis (employee of owner) or (owner or operator)

of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Larry Curtis
Box 1389, Great Bend, KS 67530
(Address)

Subscribed and sworn to before me this 9th day of Oct., 1980

Wanda Nichols
Notary Public.

My commission expires 12-10-83



DRILLER'S WELL LOG

DATE COMMENCED: 10-2-80
DATE COMPLETED: 10-6-80

The Tipton Corp.
Woydziak #1
NW NW NW Sec. 30-16-12
Barton County, KS

ELEVATIONS K.B.
 G.L.

FORMATION DATA

3060-3065'	Shale
3065-3078'	Lime
3078-3096'	Lime
3096-3154'	Shale
3154-3165'	Lime & Shale
3165-3415'	Lime
3415-3423'	Shale, Lime, Chert & Sand
3423'	RTD

Anhydrite	
Heebner	3060'
Toronto	3078'
Douglas	3096'
Brown Lime	3154'
Lansing Kansas City	3165'
Conglomerate	3415'
RTD	3423'

SURFACE PIPE:

Set @ 276' 8 5/8" 28#
used Casing w/175 sks
60/40 Pozmix 2% Gel
3% c.c.

PLUGGING:

Mud to 480' w/50 sks
50/50 Pozmix 4% Gel
Mud to 270' w/30 sks
Mud to 40' w/1/2 sks hull &
10 sks 5 sks in rathole
10-6-80

RECEIVED
STATE CORPORATION COMMISSION

OCT 15 1980

CONSERVATION DIVISION
Wichita, Kansas


AFFIDAVIT

STATE OF KANSAS)
COUNTY OF BARTON) ss.

Larry Curtis, of lawful age, does swear and state that the facts and statements herein contained are true and correct to the best of his knowledge.

Larry Curtis

Subscribed and sworn to before me this 9th day of Oct. 1980



Ulaona Nichols
(Notary Public)

My commission Expires: 12-10-83