


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 North Market, Insurance Bldg.
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above Section Plat

Barton County, Sec. 31 Twp. 16S Rge. 12 ~~XXX~~ (W)
Location as "NE/CNW/SW" or footage from lines NE NW SE
Lease Owner H-30, Inc.
Lease Name Charles Well No. 1
Office Address 200 North Main, Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed July 17, 19 64
Application for plugging filed July 17, 19 64
Application for plugging approved July 17, 19 64
Plugging commenced July 17, 19 64
Plugging completed July 17, 19 64
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Donald Truan
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3,460 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	488'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled hole with heavy rotary mud from rotary total depth (3,460') to 350 feet. Set bottom plug at 350 feet and cemented with hulls and 25 sacks cement. Filled hole with heavy rotary mud to 40 feet. Set top plug at 40' and cemented with hulls and 10 sacks cement, 2 sacks cement in rat hole.

RECEIVED
STATE CORPORATION COMMISSION

JUL 22 1964

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor H-30, Inc.
Address 200 North Main, Wichita, Kansas

STATE OF Kansas COUNTY OF Sedgwick, ss.
Garnet B. Douthit (employee of owner) ~~owner or operator~~ of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Garnet B. Douthit
200 North Main, Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 22nd day of July, 19 64
Geraldine Hays
Geraldine Hays Notary Public.

My commission expires December 3, 1964

15-009-06728-00-00

KANSAS GEOLOGICAL SOCIETY
KANSAS WELL LOG BUREAU - KANSAS WELL SAMPLE BUREAU
KANSAS GEOLOGICAL SOCIETY BUILDING
508 EAST MURDOCK - WICHITA, KANSAS


COMPANY H-30, Inc.
FARM Charles NO. 1

SEC. 31 T. 16S R. 12W
LOC. NE NW SE

TOTAL DEPTH 3,460'
COMM. 7-11-64 COMP. 7-17-64
SHOT OR TREATED
CONTRACTOR H-30, Inc.
ISSUED

COUNTY Barton

KANSAS



CASING
20 10
15 8 5/8" 488' cem. w/225 SX
12 6
13 5

1939 GL
ELEVATION 1942 DF
1944 KB
PRODUCTION

FIGURES INDICATE BOTTOM OF FORMATIONS

Top Soil	30
Shale & Shells	442
Sand	465
Red Bed	488
Shale, shells & red bed	852
Anhydrite	887
Shale & shells	1510
Lime & Shale	2000
Shale & Lime	2880
Lime & Shale	3325
Lime	3384
Lime & Shale	3460
Rotary Total Depth	3460

Sample Tops

Anhydrite Top	852	+1092
Anhydrite Base	887	+1057
Topeka	2796	- 852
Queen Hill	2991	-1047
Heebner	3079	-1135
Brown Lime	3169	-1225
Lansing	3184	-1240
Conglomerate	3420	-1476
Arbuckle	3448	-1504
Rotary T. D.	3460	-1516

RECEIVED
STATE CORPORATION COMMISSION

JUL 22 1964

INSERVATION DIVISION
Wichita, Kansas

I hereby certify that the above and foregoing is a true and correct log of the above described well as shown by the drilling reports.

H-30, INC.

Garnet B. Douthit
Garnet B. Douthit

STATE OF KANSAS)
SEDGWICK COUNTY) SS:

Subscribed and sworn to before me, a Notary Public in and for said county and state, this 22nd day of July, 1964.

Geraldine Hays
Geraldine Hays, Notary Public

My Commission Expires:
December 3, 1964.