

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 009-23-858-00-00

LEASE NAME Charles

WELL NUMBER 1

 Ft. from S Section Line

 Ft. from E Section Line

SEC. 31 TWP. 16 RGE. 12 (E) or (W)

COUNTY Barton

Date Well Completed unknown

Plugging Commenced 10-30-85

Plugging Completed 11-6-85

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Rich Ulite & John J. Darrah

ADDRESS 412 E. Douglas, Suite #1, Wichita, Kansas

PHONE# (316) 263-2243 OPERATORS LICENSE NO. 5088

Character of Well oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? yes

Which KCC/KDHE Joint Office did you notify? District #6

Is ACO-1 filed? yes If not, is well log attached?

Producing Formation unknown Depth to Top 3140 Bottom 3310 T.D. 3445

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8 5/8"	393	0
				4 1/2"	3431	2511

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

Bottom plug sand from 3400' to 3100' 4 sks. cement cap.

Top plug 500# hulls 200 sks 60-40 pos mix 6% gel

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Great Bend Casing Pullers, Inc. License No. 4635 CP

Address P. O. Box 768, Great Bend, Kansas 67530

STATE OF Kansas COUNTY OF Barton, ss.

Wes Siroky (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.


(Signature) Wes Siroky

(Address) Box 768, Great Bend, Kansas 67530

SUBSCRIBED AND SWORN TO before me this 6th day of November, 1985

Carmen R Cook

Notary Public



RECEIVED 12-12-86
STATE CORPORATION COMMISSION

NOV 7 1985

11-7-85

CONSERVATION DIVISION

Form CP-4
Revised 08-84

Wichit Properties

#1 Charles

MALLARD DRILLING CO., INC.
405 CENTURY PLAZA BLDG.
WICHITA, KANSAS 67202

DESCRIPTION:
NE SE SE 31-16S-12W

LOG NO.: 1

15-009-23858-0000

COUNTY: Barton

TOTAL DEPTH: 3445'

ELEVATION:

COMMENCED: January 21, 1985

COMPLETED: January 27, 1985

LOG RECORD:


Surface: 9 jts 8 5/8" x 23# casing
Production: 84 jts 4 1/2" x 10.5# casing

FORMATION	FROM	TO	REMARKS
Clay, shale	0	847	Ran 9 jts. 8 5/8" x 23# casing set @
Anhydrite	847	867	393'. Cement w/ 215 sx. 60/40 pozmix
Shale	867	2396	3% cc, 2% gel. PD @ 5:00 a.m. 1/22/85.
Shale w/lime	2396	3035	CDC-Allied.
Lime and shale	3035	3354	
Cong and Arbuckle	3354	3445	Ran 2 Drill Stem Tests
			Ran 84 jts. used 4 1/2" x 10.5# casing set @ 3429.5'. Cement w/ 150 sx 60/40 pozmix, 3% cc, 2% gel. PD @ 2:30 p.m. 1/27/85. Allied (10 sx salt flush)

E OF KANSAS)
) SS.
TY OF SEDGWICK)

I, JOHN JAY DARRAH, JR. of MALLARD DRILLING CO., INC., certify
this a true and correct copy of the log of the #1 Charles
to the best of my knowledge.

John Jay Darrah, Jr.
John Jay Darrah, Jr. President



Subscribed and sworn to before me this 8th day of March

Patricia C. Byrd
Notary Public

RECEIVED
STATE CORPORATION COMMISSION

OCT 7 1985

CONSERVATION DIVISION
Wichita, Kansas

Commission expires: