

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.--82-3-117

API NUMBER 15-185-20,208-A

LEASE NAME Smith (OWWO)

WELL NUMBER #1

3630 Ft. from S Section Line

1650 Ft. from E Section Line

SEC 28 TWP. 21 RGE. 14 (E) or (W)

COUNTY Stafford

Date Well Completed _____

Plugging Commenced 10-23-87

Plugging Completed 10-29-87

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Woodman-Iannitti Oil Co.

ADDRESS Box 308, Great Bend, Kansas 67530

PHONE# (316)-792-2921 OPERATORS LICENSE NO. 6558

Character of Well oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC District Office prior to plugging this well? Yes

Which KCC Office did you notify? One (1)

Is ACO-1 filed? _____ If not, is well log attached? With application

Producing Formation _____ Depth to Top _____ Bottom _____ T.D. 3880'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8-5/8"	285'	None
				4-1/2"	3865'	2,441.98'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet each set. Dumped sand to 3500' and 4 sacks cement. Shot casing at 2800, 2600' and 2400'. Pulled 58 joints of 4-1/2" casing. B.J. Titan squeezed well with 3 sacks hulls, 20 sacks cement, 5 sacks gel, and 90 sacks Econolite cement. Maximum pressure was 500 psi and shutin zero. Capped well with 1-1/2 yard readymix concrete.

11-6-1987

Name of Plugging Contractor Rockhold Engineering, Inc. LICENSE NO. 5111

Address Box 698, Great Bend, Kansas 67530 NOV 6 1987

STATE OF Kansas COUNTY OF Barton, ss.

James W. Rockhold


(Employee of Operator Wichita, Kansas) of

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) James W. Rockhold

(Address) Box 698, Great Bend, Ks. 67530

SUBSCRIBED AND SWORN TO before me this 4th day of November, 1987



My Commission Expires: _____

Iona M. Leatherman
Notary Public