


STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas 67202

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Stafford County, Sec. 28 Twp. 21S Rge. (E) 14 (W)
Location as "NE/CNW/SW" or footage from lines C NE SW NE
Lease Owner Clinton Oil Company
Lease Name E. L. Strickler Well No. 1-V
Office Address 217 N. Water, Wichita, Kansas 67202
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed September 16 19 69
Application for plugging filed Verbal Approval 19
Application for plugging approved Verbal Approval 19
Plugging commenced September 16 19 69
Plugging completed September 16 19 69
Reason for abandonment of well or producing formation _____

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Ralph J. Warren
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well _____ Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
		STATE CORPORATION COMMISSION		8 5/8"	285'	None
		SEP 24 1969				
		CONSERVATION DIVISION				
		Wichita, Kansas				

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled hole with heavy rotary mud from 3,880 feet (rotary total depth) to 450 feet. Set plug at 450 feet and cemented with 50 sacks cement. Filled hole with heavy rotary mud to 275 feet. Set plug at 275 feet and cemented with 25 sacks cement. Filled hole with heavy rotary mud to 40 feet. Set plug at 40 feet and cemented to cellar with 10 sacks cement, 2 sacks cement in rathole. All cementing done by Sun Oilwell Cementing, Inc. pump truck.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor H-30, Inc.
Address 200 N. Main St., Wichita, Kansas 67202

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
Arlo B. Romer (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Arlo B Romer
200 N. Main St., Wichita, Kansas 67202
(Address)

SUBSCRIBED AND SWORN TO before me this 23rd day of September, 19 69

My commission expires April 21, 1971

Martha Hartpence
Martha Hartpence
Notary Public.

KANSAS GEOLOGICAL SOCIETY
KANSAS WELL LOG BUREAU - KANSAS WELL SAMPLE BUREAU
KANSAS GEOLOGICAL SOCIETY BUILDING
508 EAST MURDOCK - WICHITA, KANSAS

COMPANY Clinton Oil Company

SEC. 28 T. 21S R. 14W
LOC. C NE SW NE

FARM E. L. Strickler NO. 1-V

COUNTY Stafford

TOTAL DEPTH 3,880'


COMM. September 4, 1969

COMP. September 16, 1969

SHOT OR TREATED

CONTRACTOR H-30, Inc.

ISSUED



CASING

20 10
15 5/8" 285' cemented w/285 sx cement
12 6
13 5

ELEVATION 1944 KB

PRODUCTION

FIGURES INDICATE BOTTOM OF FORMATIONS

Surface Soil & Shale	285	<u>ELECTRIC LOG TOPS</u>	
Shale & Red Bed	700		
Red Bed & Shale	850	Anhydrite	846 +1098
Anhydrite	873	Heebner	3286 -1342
Shale	1460	Toronto	3309 -1365
Shale & Shells	1755	Douglas	3328 -1384
Shale & Lime	1963	Brown Lime	3403 -1459
Lime & Shale	3475	Lansing	3414 -1470
Lime	3495	Base K. C.	3639 -1695
Lime & Shale	3550	Viola	3690 -1746
Lime	3748	Simpson Shale	3729 -1785
Lime & Shale	3764	Simpson Sand	3743 -1799
Lime	3880	Arbuckle	3778 -1834
Rotary Total Depth	3880	Log T.D.	3812 -1868
		Rotary T.D.	3880 -1936

I hereby certify the above and foregoing to be a true and correct log of the above described well as shown by the drilling reports.

H-30, INC.

RECEIVED
STATE CORPORATION COMMISSION
SEP 24 1969
CONSERVATION DIVISION
Wichita, Kansas

Arlo B. Romer
Arlo B. Romer

STATE OF KANSAS }
COUNTY OF SEDGWICK } SS:

Subscribed and Sworn to before me a Notary Public in and for said county and state this 23rd day of September, 1969.

Martha Hartpence
Martha Hartpence, Notary Public

My Commission Expires:

April 21, 1971