


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bliffing Building
Wichita, Kansas

NORTH



Stafford County. Sec. 28 Twp. 21 Rge. (E) 14 (W)
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines NE SW SE
Lease Owner Pickrell Drilling Company et al.
Lease Name Keenan Well No. 1
Office Address 705 4th Natl. Bk. Bldg., Wichita 2, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed 1/14/19 52
Application for plugging filed 1/15/19 52
Application for plugging approved 1/15/19 52
Plugging commenced 1/15/19 52
Plugging completed 1/15/19 52
Reason for abandonment of well or producing formation D. & A.

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Mr. C. D. Stough
Producing formation Depth to top Bottom Total Depth of Well 3880 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out	
				8 5/8"	270'	None	
		No Oil String was run.					

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled hole with heavy bud to 270', bridged hole & run 25 sacks of cement.
Mud hole to 35', bridge hole & ran 10 sacks of cement to bottom of cellar.

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to Globe Oilwell Cementing Co. & Pickrell Drilling Co.
Address 705 4th Natl. Bk. Bldg., Wichita 2, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.
C. W. Sebitts, Attorney-In-Fact (employee of owner) or (owner or operator) of the above-described well,
being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) *C. W. Sebitts*
705 4th Natl. Bk. Bldg., Wichita 2, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 1st day of February, 1952.

Ethel Zimmerman
Notary Public.

My commission expires January 28, 1953

28-5091-s 8-50-10M

PLUGGING
FILED 21 21 140
131 30

FEB 2 X 1952
CONSERVATION DIVISION
Wichita, Kansas
2-2-1952

COMPANY: PICKRELL DRILLING COMPANY ET AL. Rotary drilling Commenced: 1-4-52
 Wichita, Kansas Rotary Drilling Completed: 1-15-52

LOCATION: KEENAN #1, NE SW SE,
 Sec. 28-21-14W, Stafford County, Kansas

CONTRACTOR: PICKRELL DRILLING COMPANY
 Wichita, Kansas

CASING RECORD: 9 Jts. 8 5/8" Casing, set at 270' and cemented with 200 sacks cement
 in a 12 1/4" hole. Circulated cement.

LOG

(Figures indicate bottom formation - measurements from top rotary bushing.)

Clay & Sand	190	Circulate for samples at	3507'
Sand & Shale	270	" " " "	3528'
Sand	330	" " " "	3562'
Shale	780	" " " "	3599'
Red Bed	850	" " " "	3750'
Anhydrite	875	" " " "	3880'
Shale & Shells	1700		
Shale Lino	1915	Slope Test at 3000' - 0° off.	
Sandy Lino	2220		
Sandy Lino & Shale	2280		
Shale	2375		
Shale & Shells	2770		
Lino	2880		
Shale & Lino	2985		
Lino	3000		
Lino & Shale	3135		
Lino	3240		
Lino & Shale	3305		
Lino	3348		
Shale	3420		
Lino	3570		
Cherty Shale	3730		
Shale & Lino	3810		
Lino	3837		
Shale	3880		
Lino	3880	Rotary T.D.	

FEB 17 1952

The undersigned, C. W. Sebitts, Attorney-In-Fact for PICKRELL DRILLING COMPANY, hereby certifies in behalf of said Company, that the above log is a true and correct log of the formation encountered in drilling the above well as reflected by the Daily Drilling Reports.

PICKRELL DRILLING COMPANY
 By C. W. Sebitts
 Attorney-in-Fact

STATE OF KANSAS)
 COUNTY OF SEDWICK) SS

BE IT REMEMBERED that on this 1st day of February, 1952, before me, the undersigned, a Notary Public, duly commissioned, in and for the county and state aforesaid, came C. W. Sebitts, Attorney-In-Fact, and to be the same person who executed the foregoing instrument of writing in behalf of said Company, and he duly acknowledged the execution of the same for himself and for said Company.

IN WITNESS WHEREOF, I have hereunto set my hand and official seal on the day and year last above written.

C. H. Zimmerman
 Notary Public

My commission expires January 28, 1953.

PLUGGING
 SEC 21 T 21 R 14W
 PAGE 131 L 20