

STATE OF KANSAS  
STATE CORPORATION COMMISSION

Form CP-4

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

Stafford County. Sec. 27 Twp. 21S Rge. 14 (E) (W) X

Location as "NE/CNW/SW" or footage from lines SE NW SW

Lease Owner Union Texas Petroleum

Lease Name Keenan Well No. B-2

Office Address 1740 Broadway Denver Colorado H. E. Rosenberg

Character of Well (completed as Oil, Gas or Dry Hole) \_\_\_\_\_

Date well completed \_\_\_\_\_ 19\_\_

Application for plugging filed 3-18-66 19\_\_

Application for plugging approved 3-19-66 19\_\_


Plugging commenced 3-25-66 19\_\_

Plugging completed 6-4-66 19\_\_

Reason for abandonment of well or producing formation \_\_\_\_\_

If a producing well is abandoned, date of last production \_\_\_\_\_ 19\_\_

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes



Locate well correctly on above Section Plot

Name of Conservation Agent who supervised plugging of this well Archie V. Elving

Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 3798 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	1440	None
				5 1/2	None	2900

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Moved in. Rigged up unit. Broke off tubing head and well connections. Dug out cellar. Rigged up jacks. Unpacked head. Had 22" tension at 25 joints. Ran fluid plug. Plugged off bottom. Loaded hole.

Ran weight to clear hole for shot. Found fluid at 365'. Shot pipe at 2870'.

Pulling pipe.

Pulling pipe. Pumped down cellar to pack off head with 5 1/2 nipple. Closed well in.

Squeezed well with 10 sacks of mud and 80 sacks of cement. Well completed.

6-10-66  
RECEIVED  
CONSERVATION COMMISSION  
JUN 10 1966

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Forbes Casing Pulling, Inc.  
Address P. O. Box 221 Great Bend, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.

J. O. Forbes (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) J. O. Forbes  
P. O. Box 221 Great Bend, Kansas  
(Address)

SUBSCRIBED AND SWORN to before me this 8 day of June, 19 66

My commission expires May 27, 1969

Notary Public.

KEENAN "B" #2 WELL

LOCATION: SE $\frac{1}{4}$  NW $\frac{1}{4}$  SW $\frac{1}{4}$  Sec. 27-21S-14W      SPUDDED: 9-12-51  
Stafford County, Kansas

OPERATOR: Anderson-Prichard Oil Corporation      COMPLETED: 9-25-51

CONTRACTOR: Birmingham-Bartlett Drilling Co.

SURFACE CASING: 8-5/8" casing cemented at 440'  
with 350 sacks cement and 3 c.c.

OIL STRING: 5-1/2" casing cemented at 3797'  
with 125 sacks cement

L O G

(Figures indicate bottom of formation)

0	to	140	Sand
		210	Shale & Shells
		255	Clay
		320	Sand & Shale
		425	Redbed & Shale
		660	Redbed & Shells
		890	Redbed
		900	Anhydrite
		1690	Shale & Shells
		1955	Lime & Shale
		2280	Shale & Shells
		2925	Lime & Shale
		3095	Lime
		3160	Lime & Shale
		3255	Lime
		3310	Lime & Shale
		3395	Shale
		3650	Lime
		3705	Shale & Lime
		3740	Cherty Lime
		3753	Lime & Sand
		3775	Shale
		3790	Lime
		3798	Total Depth (Corrected)

RECEIVED  
STATE CORPORATION COMMISSION

APR 1 1966

CONSERVATION DIVISION  
Wichita, Kansas

The undersigned, Richard Hindery of the Birmingham-Bartlett Drilling Co., hereby certifies that the above is a true and correct log of the formations encountered in drilling the Keenan "B" #2 well as shown on the daily drilling reports.

BIRMINGHAM-BARTLETT DRILLING CO.

By Richard Hindery

Subscribed and sworn before me  
this 26th day of September, 1951

Virgil L. Zenger  
Notary Public

My commission expires November 29, 1954.