

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

15.185.00447.0600

API NUMBER Spud 12-30-1950

LEASE NAME Gates B

WELL NUMBER #1

330 Ft. from S Section Line

2310 Ft. from <sup>West</sup> Section Line

SEC. 27 TWP. 21S RGE. 14W (E) or (W)

COUNTY Stafford

Date Well Completed 1951

Plugging Commenced 12-13-94

Plugging Completed 12-13-94

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

LEASE OPERATOR American Warrior, Inc.

ADDRESS P.O. Box 399, Garden City, KS. 67846

PHONE#(316) 275-2963 OPERATORS LICENSE NO. 4058

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on December 12, 1994 (date)

by District #1 Steve Middleton (KCC District Agent's Name).

Is ACO-1 filed? Yes If not, is well log attached? Yes

Producing Formation \_\_\_\_\_ Depth to Top 3532' Bottom T.D. 3782'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
	Surface	0	250	8-5/8"	250'	NONE
	Production	0	3782	5-1/2"	3782'	NONE

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.  
Ran 2-3/8" tubing, tagged CIBP @ 3490', pulled tubing to 3455', pumped 25 sacks  
60/40 poz 6% gell, pulled tubing to 869', circulated. 8-5/8" & 5-1/2" casing with  
300 sacks of cement. Filled hole to surface.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor American Warrior, Inc. License No. \_\_\_\_\_

Address P.O. Box 399, Garden City, KS. 67846

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: American Warrior, Inc.


STATE OF Kansas COUNTY OF Finney, ss.

Kevin Wiles Sr.

(Employee of Operator) or (Operator) o above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above-described well as filed the the same are true and correct, so help me God.

(Signature) *Kevin Wiles Sr.*

(Address) P.O. Box 399, Garden City, KS. 67846



SWORN TO before me this 15th day of Dec, 1994

*Debra J. Purcell*  
Notary Public

My Commission Expires: Nov 4 1995

RECEIVED  
STATE CORPORATION COMMISSION  
DEC 16 1994  
CONSERVATION DIVISION  
WICHITA, KANSAS