

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15.185.10908.0000

LEASE NAME Pile

WELL NUMBER #2

SPOT LOCATION NW NW SE

SEC. 27 TWP 21 RGE. 14 (E) or (W)

COUNTY Stafford

Date Well Completed 7-13-51

Plugging Commenced 1-29-86

Plugging Completed 2-6-86

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Kaiser-Francis Oil Company

ADDRESS Box 666, Ellinwood, Kansas 67526

PHONE # (316)-564-2670 OPERATORS LICENSE NO. 6568

Character of Well Oil
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? One (1)

Is ACO-1 filed? If not, is well log attached? With application

Producing formation Depth to top bottom T.D. 3810"

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8-5/8"	437'	None
				5-1/2"	3807'	1,932-10'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set.

Dumped sand to 3480' and 5 sacks cement. Shot casing at 2750', 2600', 2400', 2200' and 2000'. Pulled 61 joints of 5-1/2" casing. B.J. Titan squeezed well with 3 sacks hulls, 10 sacks gel, 50 sacks cement, 10 sacks gel, 1 sack hulls, released plug and pumped 120 sacks 60/40 pozmix cement with 6% added gel. Maximum pressure was 500 psi and shut in 200 psi.

Name of Plugging Contractor Rockhold Engineering, Inc. License No. 5111

Address Box 698, Gt. Bend, Ks. 67530

STATE OF Kansas COUNTY OF Barton, ss.

James W. Rockhold (employee of operator) or (operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) James W. Rockhold
(Address) Box 698, Gt. Bend, Ks. 67530

SUBSCRIBED AND SWORN TO before me this 10th day of February 1986



IONA M. LEATHERMAN
Barton County, Kansas
My Appt. Exp. 9-26-87

Iona M. Leatherman
STATE CORPORATION COMMISSION Notary Public

My Commission expires:

FEB 11 1986

Form CP-4