

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Bldg.  
Wichita, Kansas 67202

Form CP-4  
Rev. 12-15-80

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit

COUNTY Stafford SEC. 27 TWP. 21s RGE. 14W E/W  
Location as in quarters or footage from lines:  
SW 1/4


Locate Well  
correctly on above  
Section Platt.

Lease Owner Kaiser-Francis Oil Company  
Lease Name Gates B-6 Well No. \_\_\_\_\_  
Office Address Box 666 Ellinwood, Kansas 67526  
Character of Well (Completed as Oil, Gas or Dry Hole): \_\_\_\_\_  
Date Well Completed \_\_\_\_\_  
Application for plugging filed \_\_\_\_\_  
Plugging commenced 7-24-82  
Plugging completed 8-3-82  
Reason for abandonment of well or producing formation \_\_\_\_\_

Depleted

Was permission obtained from the Conservation Division or it's  
Agent's before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well J.H. Metz

Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ bottom \_\_\_\_\_ T.D. 3778'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
				8-5/8"	260'	none
				5-1/2"	3777'	1933'

Describe in detail the manner in which the well was plugged, indicating where the mud  
fluid was placed and the method or methods used in introducing it into the hold. If cement  
or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet  
to \_\_\_\_\_ feet for each plug set.

Plugged off bottom with sand to 3380' and ran 5 sacks cement. Shot casing @2312', 2192',  
2100', 1927'. pulled 60 joints of 5-1/2" casing. Plugged well with 4 sacks hulls,  
20 sacks gel, 150 sacks 50/50 pos, 4% gel, 3% cc.

Plugging Complete.

RECEIVED  
STATE CORPORATION COMMISSION

AUG 09 1982

CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Kelso Casing Pulling

STATE OF Kansas COUNTY OF Rice, ss.


R. Darrell Kelso (employee of owner) or (owner or operator) of the  
above-described well, being first duly sworn on oath, says: That I have knowledge of the  
facts, statements, and matters herein contained and the log of the above-described well as  
filed and that the same are true and correct. So help me God.

(Signature) R. Darrell Kelso

Box 347 Chase, Kansas 67524  
(Address)

SUBSCRIBED AND SWORN TO before me this 6th day of August, 19 82

My Commission expires:



Irene Hoover  
Notary Public.