

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

15-185-10804.0000

API NUMBER None

LEASE NAME Gates B

WELL NUMBER 4

2310 Ft. from S Section Line

2970 Ft. from E Section Line

SEC. 27 TWP. 21S RGE. 14 (X) or (W)

COUNTY Stafford

Date Well Completed 5/1/91

Plugging Commenced 6/12/91

Plugging Completed 6/13/91

LEASE OPERATOR Kaiser-Francis Oil Company

ADDRESS P. O. Box 21468, Tulsa, OK 74121-1468

PHONE# (918) 494-0000 OPERATORS LICENSE NO. 6568

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 6/12/91 (verbal) (date)

by Steve Durant (KCC District Agent's Name).

Is ACO-1 filed? on old form If not, is well log attached? -

Producing Formation KC 'H' Depth to Top 3556 Bottom 3560 T.D. 3776

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
KC 'H'	Oil	3556	60	8 5/8	260	-0-
				5 1/2	3775	-0-

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set. GIH w/2 3/8" work string. Wash to 756'. Stopped. Could not wash any deeper. Pumped a 6 sx gel plug + 470 sxs 60/40 poz w/6% cc. Circ to surf. Pumped 30 sxs cmt down 8 5/8" annulus. Job complete.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Kaiser-Francis Oil Company License No. 6568

Address P. O. Box 21468, Tulsa, OK 74121-1468

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Kaiser-Francis Oil Company

STATE OF Oklahoma COUNTY OF Tulsa, ss.

Charlotte Van Valkenburg (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) C. Jan Valkenburg

(Address) P. O. Box 21468, Tulsa, OK 74121-1468

SUBSCRIBED AND SWORN TO before me this 6th day of August, 19 91

Sandra M. Mordock
Notary Public

My Commission Expires: Dec. 23, 1993

RECEIVED

AUG 08 1991

CONSERVATION DIVISION
Wichita, Kansas