


STATE OF KANSAS  
STATE CORPORATION COMMISSION

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

WELL PLUGGING RECORD



Locate well correctly on above  
Section Plat

Stafford County. Sec. 27 Twp. 21S Rge. 14 (E) (W)X  
Location as "NE/CNW/SW" or footage from lines NE NW SW  
Lease Owner Union Texas Petroleum  
Lease Name Keenan Well No. B-4  
Office Address 1740 Broadway Denver, Colorado H. E. Rosenberg  
Character of Well (completed as Oil, Gas or Dry Hole) \_\_\_\_\_  
Date well completed \_\_\_\_\_ 19\_\_\_\_  
Application for plugging filed 3-18-66 19\_\_\_\_  
Application for plugging approved 3-19-66 19\_\_\_\_  
Plugging commenced 4-7-66 19\_\_\_\_  
Plugging completed 4-11-66 19\_\_\_\_  
Reason for abandonment of well or producing formation \_\_\_\_\_

If a producing well is abandoned, date of last production \_\_\_\_\_ 19\_\_\_\_  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Archie V. Elving  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 3876 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	158	None
				5 1/2	None	1360

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Moved in. Rigged up. Shot well at 1500'. Worked pipe. Shot pipe at 1364'.  
Pulling pipe.  
Finished pulling pipe. Set overnight bridge.  
Tried to bail hole down. Dumped 5 sacks of cement.  
Bailed hole down to 330'. Dumped 20 sacks of cement. Mudded to 40'. Build  
10' rock bridge. Capped well with 10 sacks. Well Completed.

RECEIVED  
STATE CORPORATION COMMISSION  
APR 29 1966  
CONSERVATION DIVISION  
WICHITA, KANSAS

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor Forbes Casing Pulling, Inc.  
Address P. O. Box 221 Great Bend, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.  
J. O. Forbes (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) J. O. Forbes  
P. O. Box 221 Great Bend, Kansas  
(Address)

SUBSCRIBED AND SWORN TO before me this 28 day of April, 1966

My commission expires May 27, 1969 Notary Public.

KENNAM "B" #1 WELL

LOCATION: NE $\frac{1}{4}$  NW $\frac{1}{4}$  SW $\frac{1}{4}$  Sec. 27-21S-14W  
Stafford County, Kansas

OPERATOR: Anderson-Prichard Oil Corp.

CONTRACTOR: Birmingham-Bartlett Drilling Co.

SURFACE CASING: 8-5/8" 26.5# casing cemented at 147'  
with 350 sacks cement and 3 c.c.

OIL STRING: 5 $\frac{1}{2}$ " set at 3814' with 125 sacks cement.

SPUDDED: 11-9-51  
COMPLETED: 11-22-51

L O G

(Figures indicate bottom of formation)

0 to	30	Sand and clay
	200	Sand
	385	Sand, shale and shells
	448	Red bed
	855	Red bed and shells
	875	Anhydrite
	1600	Shale and shells
	1985	Broken lime
	2030	Lime
	2035	Shale and lime
	2230	Shale and shells
	2450	Shale and lime
	2980	Shale and shells
	3065	Lime and shale
	3275	Lime
	3320	Lime and shale
	3406	Shale
	3410	Brown Lime
	3696	Lime
	3699	Conglomerate
	3737	Viola
	3743	Shale
	3774	Shale and sand
	3780	Sand
	3815	Shale and Arbuckle
	3815	Total Depth.

**RECEIVED**  
STATE CORPORATION COMMISSION

APR 1 1966

CONSERVATION DIVISION  
Wichita, Kansas

The undersigned Richard Hindery of the Birmingham-Bartlett Drilling Co. hereby certifies that the above is a true and correct log of the formations encountered in drilling the Kennam B #1, as shown on the daily drilling reports.

BIRMINGHAM-BARTLETT DRILLING CO.

BY Richard Hindery

Sworn and subscribed before me  
this 23rd day of November, 1951.

Notary Public

My commission expires November 29, 1954.