

15.083.10177.0000

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 30 days from plugging date.

KANSAS CORPORATION COMMISSION OIL & GAS CONSERVATION DIVISION WELL PLUGGING RECORD K.A.R. 82-3-117

RECEIVED

OCT 27 2003

KCC WICHITA

15-083-10177-00-00

Form CP-4 September 2003 Type or Print on this Form Form must be Signed All blanks must be Filled

Lease Operator: American Warrior, Inc. Address: P.O. Box 399 Phone: (620) 275-2963 Operator License #: 4058 Type of Well: Oil Docket #: (Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (if SWD or ENHR) The plugging proposal was approved on: 10-21-03 (Date) by: Mike Maier (KCC District Agent's Name) Is ACO-1 filed? [X] Yes [] No If not, is well log attached? [] Yes [] No Producing Formation(s): List All (if needed attach another sheet) Mississippian Depth to Top: 4355' Bottom: 4370' T.D. 4370'

API Number: 15 - Drilled 1961 Lease Name: Antrim Well Number: A-1 Spot Location (QQQQ): NE - NE - 660 Feet from [X] North / [] South Section Line 660 Feet from [X] East / [] West Section Line Sec. 17 Twp. 21 S. R. 22 [] East [X] West County: Hodgeman Date Well Completed: 7-14-61 Plugging Commenced: 10-21-03 Plugging Completed: 10-21-03

Show depth and thickness of all water, oil and gas formations.

Table with columns: Oil, Gas or Water Records (Formation, Content) and Casing Record (Surface Conductor & Production) (From, To, Size, Put In, Pulled Out). Row 1: Mississippian, oil/water, 4355, 4370, 8 5/8, 271', None. Row 2: , , , , 5 1/2, 4358', None.

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed, from feet to feet each set.

Mixed & pumped 30 sacks cement with 400# of hulls and displaced to bottom with 30 sacks of gel & 68 bbls of water to plug off open hole. shut in with 550 psi. let sit 30 minutes release pressure and perforate casing @ 548', pump 110 sacks cement with 100# of hulls, pump 30 sacks down 8 5/8 braden head & held 500 psi. top off 5 1/2 casing with 40 sacks, well plugged.

Name of Plugging Contractor: Swift Services, Inc. License #: 32382 Address: Ness City, KS 67560

Name of Party Responsible for Plugging Fees: American Warrior, Inc. State of Kansas County, Ness, ss.

Scott Corsair (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) [Signature] (Address) 210 Avenue A, Bazine, KS 67516

SUBSCRIBED and SWORN TO before me this 23rd day of October 20 03

[Signature] My Commission Expires: 2/17/06 Notary Public

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

